



Tower Fertilizer System for Trimble® Field IQ™

(FmX® & FM-1000™ & TMX-2050™ displays)

Trimble Field-IQ™



Maximum Application Rates with 2 Electric Pumps

Maximum Application Rates in GPA on 30" Rows at 6 MPH (no agitation)				
Rows	8	12	16	24
Max GPA	20	12	9	5





Table Of Contents

Introduction

•	Basic Steps to Install your Fertilizer System	2
•	Complete Fertilizer System Example Drawings	3-4

Components - Liquid

•	Flowmeters, Section Valves	5-6	
•	Pressure Sensor, Pump Priming and Air Bleed Valve	7	
	Flow Indicators and Manifolds, Check Valves, Orifice Charts		
•	Dual Check Valve Systems, Row Distribution	16-19	

Components - Wiring & Electrical

U		
•	Trimble Field-IQ Rate and Section Control Module	. 21-22
	System Schematics	
•	PWM EPD	25
•	Implement Lift Switch (Mercury Run/Hold Switch)	26
	Wiring Harness Drawings	

Installation Overview

•	Floating Ball Flow Indicators, Tower Mounting Options	32-34
•	Tower 110 Plumbing Overview and Valve Operation, Recirculation	35
•	Tower 200 Plumbing Overview and Valve Operation. Agitation	36-37

Setup & Operation

•	Home Screen > System Information	38-40
	Open Field	
٠	Settings > Configuration and Firmware Upgrade	42
	Implement Setup	
	Configuration > Field-IQ > Setup and Material Setup	
	Control Setup and Section Control Setup	
•	Rate Control Setup, Pressure Sensor Setup, Implement Lift Switch Cal	51-52
•	Field-IQ > Calibration > Drive Calibration > and > Flow Calibration	53-54
•	Initial Operation Tests and Field-IQ > Diagnostics	55-56

Troubleshooting

•	Pump Will Not Run,	57-58
•	Flowmeter Troubleshooting and Tap Test	59
	Section Valve Trouble, Pressure Sensor	
•	Application Rate Fluctuates, Slow Getting to Target Rate	61
	Other Troubleshooting Issues	
	ů.	

Maintenance & Parts

•	Winterization	64
•	Pre-season Service	64



B Components Liquid



Installation Overview







Ag Systems



TAKE NOTE! THIS SAFETY ALERT SYMBOL FOUND THROUGHOUT THIS MANUAL IS USED TO CALL YOUR ATTENTION TO INSTRUCTIONS INVOLVING YOUR PERSONAL SAFETY AND THE SAFETY OF OTHERS. FAILURE TO FOLLOW THESE INSTRUCTIONS CAN RESULT IN INJURY OR DEATH.



THIS SYMBOL MEANS ATTENTION!

BECOME ALERT!

YOUR SAFETY IS INVOLVED!

Note the use of the signal words DANGER, WARNING and CAUTION with the safety messages. The appropriate signal word for each has been selected using the following guidelines:



DANGER: Indicates an imminently hazardous situation that, if not avoided, will result in death or serious injury. This signal word is to be limited to the most extreme situations typically for machine components which, for functional purposes, cannot be guarded.



WARNING: Indicates a potentially hazardous situation that, if not avoided, could result in death or serious injury, and includes hazards that are exposed when guards are removed. It may also be used to alert against unsafe practices.

CAUTION: Indicates a potentially hazardous situation that, if not avoided, may result in minor or moderate injury. It may also be used to alert against unsafe practices.

NOTICE is used to address safety practices not related to personal safety.



A Word to the Operator

SAFETY IS YOUR RESPONSIBILITY.

YOU are the key to safety.

It is YOUR responsibility to read and understand the safety messages in this manual.

This system may be used to apply many different kinds of agricultural liquid products. Read and follow all label information and instructions related to the handling, storage, and application of the product you are using.

All electrical harnessing should be checked regularly and should be routed and secured so it will not be pinched, cut, or stretched.



General Description



You have purchased a SurePoint fertilizer system for your equipment. This system will be controlled by your FM-1000[™], FmX®, CFX-750[™], FM-750, or TMX-2050 display and Field -IQ[™] Rate and Section Control Module. The rate controller will adjust the speed of the SurePoint electric pump(s) based on feedback from the flowmeter and vehicle speed. The system is capable of section control to minimize overlap areas with optional section valves.

Note for TMX-2050 Users

The setup screens shown in this manual are from the FmX or FmX Plus app on the TMX-2050 display. Most of the setup for the TMX-2050 with the FmX Plus application and FmX or FM-1000 look the same.

A big difference from prior software versions is in the Drive Calibration. The TMX-2050 and most recent FmX software uses Proportional Gain instead of Integral Gain. Run the Auto-Tuning process to get the Drive Calibration. Set the Upper PWM Limit to 100 after running the Auto-Tuning. Auto-Tuning may set the Upper PWM Limit at a lower number which limits the top end of your system.

Basic Installation Steps

- 1. Install Trimble® display, harnesses, and Field IQ[™] Rate & Section Control Module. Check with your Trimble dealer for the latest software/firmware for the display and module.
- 2. Open the packages and familiarize yourself with the components. Refer to manual sections B, C & D for component information.
- 3. Mount the Tower on your equipment.
- 4. Plumb the tank to the Tower inlet. See section E for details.
- 5. Install the plumbing kit including section valves, flow indicator columns / manifolds, check valves, plumbing to each row unit delivery point. See section B for information on these components.
- 6. Attach the flow meter outlet to section valve or manifold inlet. Attach section valve outlets to flow indicator inlets.
- 7. Attach harnesses as shown in Section D.
- 8. Setup Controller for SurePoint fertilizer system as shown in Section F.
- 9. Fill system with water, conduct initial operation and tests per Section F.
- 10. Winterize system with RV Antifreeze if freezing temperatures are expected.





Consult your Trimble Display User Guide for more information on the setup and operation of your Trimble system.



System Overview - Example 1

The following gives an example of a complete SurePoint Fertilizer system with these components:

- Trimble® Display
- Trimble® Rate & Section Control Module
- Tower 110
- Section Valves
- Flow Indicators
- Check Valves with Colored Disc Orifices



SurePoint Trimble RSCM to

twin 16 Pin Adapter Harness-



 396-001240
 Tower Fertilizer System for Field-IQ™-PWM Control
 3

 © 2011-2022
 SurePoint Ag Systems Inc.
 3



System Overview - Example 2

The following gives an example of a complete SurePoint Fertilizer system with these components:

Introduction

- Trimble® Display
- Trimble® Field-IQ Rate & Section Control Module
- Accelerator with Tower 200
- Dual Check Valve Distribution System
- Dual Metering Tube



SurePoint Trimble RSCM to

Electromagnetic Flowmeter Kits 0.13 - 2.6 GPM 0.3 - 5.0 GPM Item Number 500-02-2050

0.08 - 1.6 GPM 204-01-46211CUF05 (FM only)

Kits include flowmeter, mounting bracket, hose barb fittings & hose clamps.

Before doing any arc welding on the implement, unplug the cable to the flowmeter, or damage to the flowmeter may result.

New Look in 2017—Black body with orange label. Same accurate, reliable electromagnetic technology. 3-pin Amp SuperSeal connector is sealed to



Electromagnetic flowmeters are superior to traditional turbine flowmeters in two basic ways. First, they have no moving parts. This translates into no wear items or potential for contaminants to jam a spinning turbine.

Second, electromagnetic flowmeters detect the flow by electrically measuring the velocity of the liquid, which makes them independent of viscosity or density of the fluid measured. They are extremely accurate using the standard calibration number. SurePoint still recommends you perform a catch test to verify the system is properly installed and configured.

Flowmeter Model (orange label or blue label)	Pulses/Gal	FPT Size	Hose Barb In kit
0.13 - 2.6 GPM	3000	3/4"	3/4"
0.3 - 5.0 GPM	3000	3/4"	3/4"
0.08-1.6 GPM	22700	3/4"	3/4"



Serial number label on side also shows pulses per gallon.

Use adapter

MP harness

to connect to 3-pin

201-17842







-

FLOW

Ag Systems

0.3 - 5.0 GPM

5

Section Valves

105-100075BRB90

105-100PLG (alternate 105-100PLG025 includes 1/4" pipe thread for gauge)





OFF position, replace actuator. Pull gray pin to remove actuator from valve.

This is a 3-way valve. If product will not flow when valve is ON, either move the outlet hose to the other port, or remove actuator and rotate valve ball 180°, and replace actuator.

How it Works

Section valves can be assembled into groups with a common inlet to control flow to each section. Common assemblies use up to 5-6 valves, however, more can be used where practical. Many alternate fittings can be used to accommodate different hose sizes and configurations.

The valves have a 3-pin weather pack electrical connector. This has a power, ground, and switched signal wire. The power measured to ground should have 12 volts when the controller is on. The switched signal wire will have 12 volts to turn the valve on, and 0 volts to turn the valve off.

Wiring Connector: Pin A—Red, 12 Volts + Pin B-Black, Ground -

Pin C—White, Signal

12V=on ; 0V=off

Mounting Hardware: 2 Valve Bolt Kit 384-1100 **Mounting Bracket** 400-2493Y1



Pressure Sensor

The Tower 110 and 200 come equipped with a 100 psi (0 to 5 volt) pressure sensor to work with Trimble. This sensor is a 3 wire type sensor for compatibility with Trimble. The sensor has a 1/4" MPT fitting.

The Trimble display will show the system pressure on the in cab screen. The pressure

reading is only for informational purposes and is NOT used in the flow control process. Flow control uses the flowmeter feedback only.



There is a Main Pressure connector on both the final pump harness (207-4189Y1) and on the section harness (207-3463Y1).

The pressure transducer is factory calibrated and will display a very accurate pressure reading on the Trimble display. No manual gauge is required.

Pressure Sensor (3 wire type) with harness 521-05-050150 Trimble Pressure Calibration: 50 mv/psi

Pump Priming and Air Bleed Valve

ACHATION

SureFire

DWGM

An air bleed valve is included with each pump to aid in system priming. It is shipped in the pump accessories bag and must be installed during system installation.



Why use an air bleed valve:

Most fertilizer systems are equipped with a 4 lb or 10 lb check valve on the end of each hose delivering fertilizer to the ground. These valves do not let air escape from the system, unless it is pressurized. 12-volt liquid pumps are not good air compressors. Therefore, the pump can struggle to prime due to air trapped on the outlet side of the pump.

The air bleed valve is a small 1/4" valve that when opened lets air escape from the pump outlet at zero pressure. Open until liquid comes out and then close the valve.

How to install the air bleed valve:

Remove the 1/4" plug from the quick connect fitting on the center cross on the Tower (see picture). Next, insert the 1/4" tubing in the quick connect fitting. Run the 1/4" tubing to an easily accessible spot on your equipment. Next, cut the tubing and push the 1/4" valve onto the tubing. Finally, run the tubing to a low location where any fertilizer that escapes will run on the ground.

Be sure the air bleed valve tube does not become plugged with dirt or it will not allow the air to bleed.





Product Distribution

<u>To assure proper and even distribution to each row, the product being applied</u> <u>must be metered to each individual row.</u> This metering is done by one of the 3 following methods which create back pressure so an equal amount of liquid is applied to each row.

- 1. A metering orifice may be placed in the top cap of each floating ball flow indicator. (See photos on page 10—this is not used very often)
- 2. A metering orifice may be placed in the check valve cap in the line that leads to each row. (See photo on page 12)
- 3. A dual metering tube kit with dual check valves may be used. (See pages 16-19)

Floating Ball Flow Indicator & Manifold System

Flow indicators give a clear visual signal that a fertilizer system is working. These indicators use an o-ring and wire clip connection to snap together in any configuration necessary.

SurePoint has simple tee brackets and U-bolts that will mount these to a variety of bar sizes.

Two main types of flow indicators are used. On 30" row spacing, the low flow column with 1/4" push to connect outlet is recommended for rates under 10 GPA. For rates over 10 GPA the full flow column with 3/8" hose barb outlet is preferred.

Parts List

Complete Columns

701-20460-950Single Full Flow Column with 3/8" HB - 90 Degree Outlet701-20460-940Single Full Flow Column with 3/8" QC - 90 Degree Outlet701-20460-960Single Full Flow Column with 1/2" HB - 90 Degree Outlet701-20460-935Single Low Flow Column with 3/8" QC - 90 Degree Outlet701-20460-920Single Low Flow Column with 1/4" QC - 90 Degree Outlet

Fittings

701-20503-00	ORS x 3/4" HB - Straight
701-20511-00	ORS x 3/8" HB - 90 Degree
701-20512-00	ORS x 1/2" HB - 90 Degree
701-20513-00	ORS x 3/4" HB - 90 Degree
701-20516-00	ORS x 1/4" QC - 90 Degree
701-20517-00	ORS x 3/8" QC - 90 Degree
701-20518-00	ORS x 1/4" FPT - 90 Degree
701-20519-00	ORS x 1/4" FPT - Straight
701-20520-00	ORS Male x ORS Female - 90 degree
701-20521-00	Wilger End Cap
701-20523-00	ORS Male x ORS Female x 3/8" FPT - Isolator
701-20525-00	ORS Male x ORS Male x 1" FPT - Tee

Brackets & U-Bolts

400-1037A1	3-6 Row Bracket
400-3155Y1	7-12 Row Bracket
400-2011A1	White Backer Plate for 3-6 Row Bracket
400-2010A1	White Backer Plate for 7-12 Row Bracket
400-1315A2	Flow Indicator Bracket, 6-8 in wide hitch mount



Service Parts Only

	- J
701-20460-02	Wilger Flow Indicator Ball Retainer
701-20460-03	FKM O-Ring for indicator body & fittings
701-20460-04	Wilger Lock U-clip
701-20460-05	Flow Indicator Ball - 1/2" SS Ball
701-20460-06	Flow Indicator Ball - Maroon Glass
701-20460-07	Flow Indicator Ball - Red Celcon
701-20460-08	Flow Indicator Ball - Green Poly
701-20460-09	Flow Indicator Ball - Black Poly
701-20460-15	Viton O-Ring for column & fittings
701-40225-05	Viton O-Ring for Orifice







Ag Systems

Floating Ball Flow Indicators– Metering Orifice Selection for 30" Rows See www.surepointag.com for other row spacings



30" Spacing

		0.100		-			<u> </u>		
Orifice	PSI	Gal/Min 28-0-0	4.0	4.5	5.0	MPH 5.5	6.0	6.5	7.0
		· ·							
	10	0.043	2.15	1.91	1.72	1.56	1.43	1.32	1.23
	20	0.061	3.02	2.69	2.42	2.20	2.02	1.86	1.73
28	30	0.075	3.72	3.31	2.98	2.71	2.48	2.29	2.13
20	40	0.087	4.29	3.82	3.43	3.12	2.86	2.64	2.45
	50	0.097	4.82	4.28	3.85	3.50	3.21	2.97	2.75
	60	0.106	5.26	4.67	4.21	3.82	3.50	3.23	3.00
	10	0.070	3.46	3.08	2.77	2.52	2.31	2.13	1.98
	20	0.098	4.86	4.32	3.89	3.54	3.24	2.99	2.78
	30	0.120	5.96	5.30	4.77	4.33	3.97	3.67	3.40
35	40	0.120	6.88	6.11	5.50	5.00	4.58	4.23	3.93
	50	0.156	7.71	6.85	6.17	5.61	5.14	4.74	4.41
	60	0.170	8.41	7.48	6.73	6.12	5.61	5.18	4.81
	10	0.090	4.47	3.97	3.57	3.25	2.98	2.75	2.55
	20	0.127	6.31	5.61	5.05	4.59	4.21	3.88	3.60
40	30	0.157	7.75	6.89	6.20	5.64	5.17	4.77	4.43
	40	0.181	8.94	7.94	7.15	6.50	5.96	5.50	5.11
	50	0.202	9.99	8.88	7.99	7.26	6.66	6.15	5.71
	60	0.221	10.95	9.73	8.76	7.96	7.30	6.74	6.26
	10	0.119	5.91	5.26	4.73	4.30	3.94	3.64	3.38
	20	0.169	8.37	7.44	6.69	6.08	5.58	5.15	4.78
	30	0.207	10.25	9.11	8.20	7.45	6.83	6.31	5.86
46	40	0.239	11.83	10.51	9.46	8.60	7.88	7.28	6.76
	50	0.267	13.23	11.76	10.58	9.62	8.82	8.14	7.56
	60	0.293	14.50	12.89	11.60	10.55	9.67	8.92	8.29
	10	0.149	7.36	6.54	5.89	5.35	4.91	4.53	4.21
	20	0.210	10.38	9.23	8.31	7.55	6.92	6.39	5.93
52	30	0.257	12.70	11.29	10.16	9.24	8.47	7.82	7.26
	40	0.296	14.67	13.04	11.74	10.67	9.78	9.03	8.39
	50	0.332	16.43	14.60	13.14	11.95	10.95	10.11	9.39
	60	0.363	17.96	15.96	14.37	13.06	11.97	11.05	10.26
	10	0.218	10.78	9.58	8.62	7.84	7.18	6.63	6.16
	20	0.307	15.20	13.51	12.16	11.05	10.13	9.35	8.69
	30	0.376	18.62	16.55	14.89	13.54	12.41	11.46	10.64
63	40	0.435	21.51	19.12	17.21	15.64	14.34	13.24	12.29
	50	0.486	24.05	21.38	19.24	17.49	16.03	14.80	13.74
	60	0.532	26.33	23.40	21.06	19.15	17.55	16.20	15.04
	40	0.044	10.07	44.00	10.10	40.07	44.04	40.00	0.04
	10	0.341	16.87	14.99	13.49	12.27	11.24	10.38	9.64
	20 30	0.481	23.83 29.22	21.18 25.97	19.06 23.37	17.33 21.25	15.89 19.48	14.66 17.98	13.62 16.70
78	30 40			29.98		21.25	22.49	20.76	19.27
	40 50	0.681	33.73 37.72	33.53	26.98 30.17	24.53	22.49	20.76	21.55
	60	0.762	41.31	36.72	33.05	30.04	25.14	25.42	23.60
		0.000			00.00		2	20.12	20.00
	10	0.553	27.38	24.34	21.90	19.91	18.25	16.85	15.64
	20	0.782	38.72	34.42	30.98	28.16	25.82	23.83	22.13
98	30	0.956	47.31	42.05	37.85	34.41	31.54	29.11	27.03
	40	1.106	54.76	48.67	43.81	39.82	36.50	33.70	31.29
	50	1.239	61.33	54.51	49.06	44.60	40.88	37.74	35.04
	60	1.354	67.02	59.58	53.62	48.74	44.68	41.24	38.30
	10	0.649	32.11	28.54	25.69	23.35	21.41	19.76	18.35
	20	0.049	45.56	40.50	36.45	33.13	30.37	28.04	26.03
	30	1.124	55.63	40.50	44.51	40.46	37.09	34.24	31.79
107	40	1.124	64.39	57.24	51.52	46.83	42.93	39.63	36.80
	50	1.451	71.84	63.86	57.47	52.25	47.89	44.21	41.05
	60	1.584	78.41	69.70	62.73	57.03	52.27	48.25	44.81
	10	0.938	46.43	41.27	37.15	33.77	30.96	28.57	26.53
	20	1.319	65.27	58.02	52.22	47.47	43.51	40.17	37.30
130	30	1.619	80.16	71.26	64.13	58.30	53.44	49.33	45.81
	40	1.867	92.43	82.16	73.94	67.22	61.62	56.88	52.82
	50	2.088	103.38	91.89	82.70	75.19	68.92	63.62	59.07
	60	0.000							

Tower Electric Pump

Pressure Recommendations

(with 4 lb check valves):

- Minimum 10 PSI
- Maximum 30 PSI

PumpRight

Pressure Recommendations

(with 10 lb check valves):

- Minimum 20 PSI
- Maximum 80 PSI

Chart is for 28-0-0 Fertilizer @ 70°

- Heavier fertilizers (like 10-34-0) will have 5-15% less flow than chart indicates for a certain pressure
- Cold fertilizers will cause system pressure to increase at a given application rate.
- Tower Electric Pump Systems will have reduced flow and increased electrical current draw due to cold fertilizer increasing operating pressure. Use the largest orifice possible for cold weather operation.



If using a metering orifice in the flow indicator, the orifice replaces the ball retainer. If not using an orifice here, the ball retainer must be in place. Remove top fitting of each column. Then push the metering orifice into bottom of each outlet fitting.

All application rates (gallons/acres) are estimates based on 0-28-0 (10.65 lbs/gallon) at 70 degrees F.

60 2.292 113.46 100.85 90.76 82.51 75.64 69.82 64.83



SurePoint 396-001240 Tower Fertilizer System for Field-IQ™-PWM Control © 2011-2022 SurePoint Ag Systems Inc.

Check Valves

4 lb check valve with 1/4" quick connect fittings

4 lb check valves are typically used with **electric pump systems**. SurePoint recommends this valve for use with 1/4" tubing applying up to 10 GPA on 30" rows. (3/8" tube may be better for 10-34-0 or with long runs) The recommended minimum system operating pressure for this check is 10 psi, to ensure all checks open fully.



10 lb check valve with 3/8" hose barbs

The recommended check valve for most **PumpRight installations** is the 10 lb check with 3/8" hose barbs. This works with 3/8" rubber hose which SurePoint recommends for most applications over 10 GPA on 30" rows. The recommended minimum system operating pressure for this check is 20 psi, to ensure all checks open fully.



Special Purpose Check Valve Assemblies

Assembly Part Number	Description	Suggested Uses (30" rows)
136-10-04QC04QC	1/4" QC x 1/4" QC 10 lb	< 10 GPA with PumpRight & 1/4" Tubing
136-10-06QC06QC	3/8" QC x 3/8" QC 10 lb	With 3/8" tubing plumbing
136-04-06HB06HB	3/8" HB x 3/8" HB 4 lb	> 10 GPA with Electric Pumps
136-04-08HB08HB	1/2" HB x 1/2" HB 4 lb	> 50 GPA with PumpRight
136-10-08HB08HB	1/2" HB x 1/2" HB 10 lb	> 50 GPA with PumpRight



Components Liquid

Complete Assembly

PN 136-10-06HB06HB

Colored Disc Orifice Chart for 30" rows



		30)"	Sp	ac	ing	3		
Orifice	r						•		
Color (Approx	PSI	Gal/Min 28-0-0	4.0	4.5	5.0	MPH 5.5	6.0	65	7.0
(Approx L Size)	P31	20-0-0	4.0	4.0	5.0	0.0	0.0	6.5	7.0
51267	10	0.033	1.62	1.44	1.30	1.18	1.08	1.00	0.93
F	20	0.046	2.28	2.02	1.82	1.66	1.52	1.40	1.30
	30	0.057	2.80	2.49	2.24	2.04	1.87	1.73	1.60
Pink (24)	40	0.065	3.24	2.88	2.59	2.36	2.16	1.99	1.85
[50	0.073	3.64	3.23	2.91	2.64	2.42	2.24	2.08
	60	0.081	3.99	3.54	3.19	2.90	2.66	2.45	2.28
	10	0.050	2.50	2.22	2.00	1.82	1.66	1.54	1.43
-	20	0.072	3.55	3.15	2.84	2.58	2.37	2.18	2.03
Gray (30)	30	0.088	4.34	3.85	3.47	3.15	2.89	2.67	2.48
	40	0.101	4.99	4.44	4.00	3.63	3.33	3.07	2.85
-	50 60	0.112 0.124	5.56 6.13	4.95 5.45	4.45	4.05 4.46	3.71 4.09	3.42 3.77	3.18 3.50
	00	0.124	0.15	0.40	4.91	4.40	4.09	3.11	3.00
	10	0.070	3.46	3.08	2.77	2.52	2.31	2.13	1.98
-	20	0.098	4.86	4.32	3.89	3.54	3.24	2.99	2.78
	30	0.120	5.96	5.30	4.77	4.33	3.97	3.67	3.40
Black (35)	40	0.139	6.88	6.11	5.50	5.00	4.58	4.23	3.93
	50	0.156	7.71	6.85	6.17	5.61	5.14	4.74	4.41
	60	0.170	8.41	7.48	6.73	6.12	5.61	5.18	4.81
-	10	0.094	4.64	4.13	3.71	3.38	3.10	2.86	2.65
Busin	20	0.132	6.53	5.80	5.22	4.75	4.35	4.02	3.73
Brown	30 40	0.162	8.02 9.24	7.13 8.22	6.41	5.83	5.34	4.93 5.69	4.58
(41)	40 50	0.187	9.24	9.19	7.39 8.27	6.72 7.52	6.16 6.89	6.36	5.20
-	60	0.203	11.30	10.05	9.04	8.22	7.53	6.95	6.46
ļ		0.220		10.00	0.01	0.22	1.00	0.00	0.10
	10	0.119	5.91	5.26	4.73	4.30	3.94	3.64	3.38
	20	0.169	8.37	7.44	6.69	6.08	5.58	5.15	4.78
Orange	30	0.207	10.25	9.11	8.20	7.45	6.83	6.31	5.86
(46)	40	0.239	11.83	10.51	9.46	8.60	7.88	7.28	6.76
-	50	0.267	13.23	11.76	10.58	9.62	8.82	8.14	7.56
	60	0.293	14.50	12.89	11.60	10.55	9.67	8.92	8.29
	10	0.149	7.36	6.54	5.89	5.35	4.91	4.53	4.21
	20	0.149	10.38	9.23	8.31	7.55	6.92	6.39	5.93
Maroon	30	0.257	12.70	11.29	10.16	9.24	8.47	7.82	7.26
(52)	40	0.296	14.67	13.04	11.74	10.67	9.78	9.03	8.39
(,	50	0.332	16.43	14.60	13.14	11.95	10.95	10.11	9.39
	60	0.363	17.96	15.96	14.37	13.06	11.97	11.05	10.26
	10	0.218	10.78	9.58	8.62	7.84	7.18	6.63	6.16
	20	0.307	15.20	13.51	12.16	11.05	10.13	9.35	8.69
Red (63)	30	0.376	18.62	16.55	14.89	13.54	12.41	11.46	10.64
· · /	40	0.435	21.51	19.12	17.21	15.64	14.34	13.24	12.29
ŀ	50 60	0.486	24.05	21.38 23.40	19.24 21.06	17.49 19.15	16.03	14.80 16.20	13.74 15.04
	00	0.532	26.33	23.40	21.00	19.10	17.55	10.20	15.04
	10	0.351	17.39	15.46	13.91	12.65	11.59	10.70	9.94
	20	0.496	24.57	21.84	19.66	17.87	16.38	15.12	14.04
	30	0.608	30.09	26.75	24.08	21.89	20.06	18.52	17.20
Blue (80)	40	0.702	34.74	30.88	27.79	25.26	23.16	21.38	19.85
	50	0.785	38.86	34.54	31.08	28.26	25.90	23.91	22.20
	60	0.859	42.53	37.81	34.03	30.93	28.36	26.18	24.31
	10	0.506	25.06	22.27	20.05	18.22	16.70	15.42	14.32
Valley	20	0.715	35.39	31.46	28.32	25.74	23.60	21.78	20.23
Yellow	30	0.876	43.37	38.55	34.69	31.54	28.91	26.69	24.78
(95)	40	1.009 1.133	49.94 56.07	44.39 49.84	39.95	36.32	33.29	30.73	28.54 32.04
	50 60	1.133	61.33	49.84 54.51	44.86	40.78 44.60	37.38 40.88	34.51 37.74	32.04
	00	1.209	01.00	10.70	-0.00	00.77	-0.00	01.14	00.04
	10	0.686	33.95	30.18	27.16	24.69	22.63	20.89	19.40
ŀ	20	0.973	48.19	42.83	38.55	35.04	32.12	29.65	27.53
Green	30	1.186	58.70	52.18	46.96	42.69	39.13	36.12	33.54
(110)	40	1.372	67.90	60.35	54.32	49.38	45.27	41.78	38.80
		1 504	75 70	07.00	<u> </u>	FF 40		40.04	40.00
ìí	50	1.531	75.78	67.36	60.63	55.12	50.52	46.64	43.30

Tower Electric Pump Pressure Recommendations (with 4 lb check valves):

- Minimum 10 PSI
- Maximum 30 PSI (pump can do 50 PSI or more if total output is not too great)

PumpRight Pressure

Recommendations (with 10 lb check valves):

- Minimum 20 PSI
- Maximum 80 PSI

Chart is for 28-0-0 Fertilizer @ 70°

- Heavier fertilizers (like 10-34-0) will have 5-15% less flow than chart indicates for a certain pressure
- Cold fertilizers will cause system pressure to increase at a given application rate.
- Tower Electric Pump Systems will have reduced flow and increased electrical current draw due to cold fertilizer increasing operating Use the largest orifice pressure. possible for cold weather This is operation. absolutely essential for 24-row systems using electric pumps.

Colored Disc Orifice assembles under the check valve cap in most cases. (Drop the orifice with the hole down into the cap, then put the gasket on top of it.) The orifice can also be installed in a manifold (common on grain drills).



Ag Systems

Colored Disc Orifice Chart Common Grain Drill Row Spacings



7.5" Spacing										10" Spacing									
Orifice	-	0.1/22								Orifice	F	Cal/Mar				MELL			<u> </u>
Color	201	Gal/Min	4.0			MPH				Color (Approx	PSI	Gal/Min 28-0-0	4.0	4.5	5.0	MPH 5.5	6.0	6.5	7.0
(Approx Size)	PSI	28-0-0	4.0	4.5	5.0	5.5	6.0	6.5	7.0	Size)	P31	20-0-0	4.0	4.5	5.0	5.5	0.0	0.5	7.0
0120)	10	0.033	6.5	5.8	5.2	4.7	4.3	4.0	3.7	0.20)	10	0.033	4.9	4.3	3.9	3.5	3.2	3.0	2.8
	20	0.046	9.1	8.1	7.3	6.6	6.1	5.6	5.2		20	0.046	6.8	6.1	5.5	5.0	4.6	4.2	3.9
Pink (24)	30	0.057	11.2	10.0	9.0	8.2	7.5	6.9	6.4	Pink (24)	30	0.057	8.4	7.5	6.7	6.1	5.6	5.2	4.8
(,	40 50	0.065	13.0	11.5	10.4	9.4	8.6 9.7	8.0	7.4	(= .)	40 50	0.065	9.7 10.9	8.6 9.7	7.8 8.7	7.1	6.5 7.3	6.0 6.7	5.6 6.2
	50 60	0.073	14.5 15.9	12.9 14.2	11.6 12.8	10.6 11.6	9.7	8.9 9.8	8.3 9.1		60	0.073	12.0	9.7	9.6	8.7	8.0	7.4	6.8
											10	0.050							
	10 20	0.050	10.0 14.2	8.9 12.6	8.0 11.4	7.3	6.7 9.5	6.1 8.7	5.7 8.1		10 20	0.050 0.072	7.5	6.7 9.5	6.0 8.5	5.4 7.7	5.0 7.1	4.6 6.6	4.3 6.1
	30	0.072	17.3	12.0	13.9	12.6	11.6	10.7	9.9		30	0.072	13.0	11.6	10.4	9.5	8.7	8.0	7.4
Gray (30)	40	0.101	20.0	17.8	16.0	14.5	13.3	12.3	11.4	Gray (30)	40	0.101	15.0	13.3	12.0	10.9	10.0	9.2	8.6
	50 60	0.112	22.3 24.5	19.8 21.8	17.8 19.6	16.2 17.8	14.8 16.4	13.7 15.1	12.7 14.0		50 60	0.112	16.7 18.4	14.8 16.4	13.4 14.7	12.1 13.4	11.1 12.3	10.3 11.3	9.5 10.5
	60	0.124	24.5	21.0	19.0	17.0	10.4	15.1	14.0		00	0.124	10.4	10.4	14.7	13.4	12.5	11.5	10.5
	10	0.070	13.8	12.3	11.1	10.1	9.2	8.5	7.9		10	0.070	10.4	9.2	8.3	7.6	6.9	6.4	5.9
	20	0.098	19.4 23.8	17.3	15.6	14.1	13.0 15.9	12.0	11.1		20 30	0.098	14.6 17.9	13.0 15.9	11.7 14.3	10.6 13.0	9.7	9.0 11.0	8.3 10.2
Black (35)	30 40	0.120	23.8	21.2 24.5	19.1 22.0	17.3 20.0	15.9	14.7 16.9	13.6 15.7	Black (35)	30 40	0.120	20.6	18.3	14.3	15.0	11.9 13.8	12.7	10.2
	50	0.155	30.8	24.5	24.7	20.0	20.6	19.0	17.6		50	0.156	23.1	20.6	18.5	16.8	15.4	14.2	13.2
	60	0.170	33.6	29.9	26.9	24.5	22.4	20.7	19.2		60	0.170	25.2	22.4	20.2	18.4	16.8	15.5	14.4
	10	0.094	19	17	15	14	12	11	11		10	0.094	14	12	11	10	9	9	8
	20	0.132	26	23	21	19	17	16	15		20	0.132	20	17	16	14	13	12	11
Brown	30	0.162	32	29	26	23	21	20	18	Brown	30	0.162	24	21	19	17	16	15	14
(41)	40 50	0.187	37 41	33 37	30	27 30	25 28	23	21	21 (41) 24	40 50	0.187	28 31	25 28	22	20 23	18 21	17	16
	60	0.209	41	40	33 36	33	30	25 28	24		60	0.209	34	30	25 27	25	23	19 21	18 19
	00	0.220	10					20											
	10	0.119	24	21	19	17	16	15	14		10	0.119	18	16	14	13	12	11	10
Orange	20 30	0.169 0.207	33 41	30 36	27 33	24 30	22 27	21 25	- 23	19 23 Orange	20 30	0.169	25 31	22 27	20 25	18 22	17 21	15 19	14 18
(46)	40	0.239	47	42	38	34	32	29	27	(46)	40	0.207	35	32	28	26	24	22	20
(,	50	0.267	53	47	42	38	35	33	30	(,	50	0.267	40	35	32	29	26	24	23
	60	0.293	58	52	46	42	39	36	33		60	0.293	43	39	35	32	29	27	25
	10	0.149	29	26	24	21	20	18	17		10	0.149	22	20	18	16	15	14	13
	20	0.210	42	37	33	30	28	26	24		20	0.210	31	28	25	23	21	19	18
Maroon	30	0.257	51	45	41	37	34	31	29	Maroon	30	0.257	38	34	30	28	25	23	22
(52)	40 50	0.296	59 66	52 58	47	43 48	39 44	36 40	34 38	(52)	40 50	0.296	44 49	39 44	35 39	32 36	29 33	27 30	25 28
	60	0.363	72	64	57	52	48	44	41		60	0.363	54	48	43	39	36	33	31
	10	0.218	43	38	34	31	29	27	25		10	0.218	32	29	26	24	22	20	18
	20	0.218	61	54	49	44	41	37	35		20	0.218	46	41	36	33	30	20	26
Red (63)	30	0.376	74	66	60	54	50	46	43	Red (63)	30	0.376	56	50	45	41	37	34	32
	40	0.435	86	76	69	63	57	53	49	(03)	40	0.435	65	57	52	47	43	40	37
	50 60	0.486 0.532	96 105	86 94	77 84	70 77	64 70	59 65	55 60		50 60	0.486 0.532	72 79	64 70	58 63	52 57	48 53	44 49	41 45
	10	0.351	70	62	56	51	46	43	40		10	0.351	52	46	42	38	35	32	30
	20 30	0.496	98 120	87 107	79 96	71 88	66 80	60 74	56 69		20 30	0.496	74 90	66 80	59 72	54 66	49 60	45 56	42 52
Blue (80)	40	0.702	139	107	111	101	93	86	79	Blue (80)	40	0.000	104	93	83	76	69	64	60
	50	0.785	155	138	124	113	104	96	89		50	0.785	117	104	93	85	78	72	67
	60	0.859	170	151	136	124	113	105	97		60	0.859	128	113	102	93	85	79	73
	10	0.506	100	89	80	73	67	62	57		10	0.506	75	67	60	55	50	46	43
	20	0.715	142	126	113	103	94	87	81	81 99 Yellow 114 (95)	20	0.715	106	94	85	77	71	65	61
Yellow	30	0.876	173	154	139	126	116	107			30	0.876	130	116	104	95	87	80	74
(95)	40 50	1.009 1.133	200 224	178 199	160 179	145 163	133 150	123 138	114 128		40 50	1.009 1.133	150 168	133 150	120 135	109 122	100 112	92 104	86 96
	60	1.239	245	218	196	178	164	150	120		60	1.133	184	164	135	134	123	104	105
		allons/acres												•					



13

Colored Disc Orifice Chart



Orifice									
Color (Approx	PSI	Gal/Min 28-0-0	4.0	4.5	5.0	MPH 5.5	6.0	6.5	7.0
Size)									
	10 20	0.033	3.2 4.6	2.9 4.0	2.6 3.6	2.4 3.3	2.2 3.0	2.0 2.8	1.9 2.6
	30	0.046	5.6	5.0	4.5	4.1	3.0	3.5	3.2
Pink (24)	40	0.065	6.5	5.8	5.2	4.7	4.3	4.0	3.7
	50	0.073	7.3	6.5	5.8	5.3	4.8	4.5	4.2
	60	0.081	8.0	7.1	6.4	5.8	5.3	4.9	4.6
	10	0.050	5.0	4.4	4.0	3.6	3.3	3.1	2.9
	20	0.030	7.1	6.3	5.7	5.2	4.7	4.4	4.1
Gray (30)	30	0.088	8.7	7.7	6.9	6.3	5.8	5.3	5.0
Gray (30)	40	0.101	10.0	8.9	8.0	7.3	6.7	6.1	5.7
	50 60	0.112	11.1 12.3	9.9 10.9	8.9 9.8	8.1 8.9	7.4 8.2	6.8 7.5	6.4 7.0
L	00	0.124	12.0	10.3	3.0	0.3	0.2	1.5	7.0
	10	0.070	6.9	6.2	5.5	5.0	4.6	4.3	4.0
Block	20	0.098	9.7	8.6	7.8	7.1	6.5	6.0	5.6
Black (35)	30 40	0.120	11.9 13.8	10.6 12.2	9.5 11.0	8.7 10.0	7.9 9.2	7.3 8.5	6.8 7.9
(,	50	0.156	15.4	13.7	12.3	11.2	10.3	9.5	8.8
	60	0.170	16.8	15.0	13.5	12.2	11.2	10.4	9.6
	10	0.094	9.3	83	7.4	6.8	62	57	53
	10 20	0.094	9.3	8.3 11.6	10.4	6.8 9.5	6.2 8.7	5.7 8.0	5.3 7.5
Brown	30	0.162	16.0	14.3	12.8	11.7	10.7	9.9	9.2
(41)	40	0.187	18.5	16.4	14.8	13.4	12.3	11.4	10.6
	50 60	0.209	20.7 22.6	18.4 20.1	16.5 18.1	15.0 16.4	13.8 15.1	12.7 13.9	11.8 12.9
	00	0.220	22.0	20.1	10.1	10.4	10.1	10.0	12.0
	10	0.119	11.8	10.5	9.5	8.6	7.9	7.3	6.8
Orange	20	0.169	16.7	14.9	13.4	12.2	11.2	10.3	9.6
(46)	30 40	0.207	20.5 23.7	18.2 21.0	16.4 18.9	14.9 17.2	13.7 15.8	12.6 14.6	11.7 13.5
,	50	0.259	26.5	23.5	21.2	19.2	17.6	14.0	15.1
	60	0.293	29.0	25.8	23.2	21.1	19.3	17.8	16.6
	10	0.149	15	13	12	11	10	9	8
	20	0.210	21	18	17	15	14	13	12
Maroon	30	0.257	25	23	20	18	17	16	15
(52)	40	0.296	29	26	23	21	20	18	17
	50 60	0.332	33 36	29 32	26 29	24 26	22 24	20 22	19 21
L	00	0.003	50	JZ	23	20	24		21
	10	0.218	22	19	17	16	14	13	12
	20	0.307	30 37	27	24	22 27	20	19	17
Red (63)	30 40	0.376	43	33 38	30 34	31	25 29	23 26	21 25
	50	0.486	48	43	38	35	32	30	27
L	60	0.532	53	47	42	38	35	32	30
	10	0.351	35	31	28	25	23	21	20
	20	0.496	49	44	39	36	33	30	28
Blue (80)	30	0.608	60	54	48	44	40	37	34
	40	0.702	69	62	56	51	46	43	40
	50 60	0.785	78 85	69 76	62 68	57 62	52 57	48 52	44 49
	10	0.506	50	45	40	36	33	31	29
Yellow	20 30	0.715	71 87	63 77	57 69	51 63	47 58	44 53	40 50
(95)	40	1.009	100	89	80	73	67	61	57
	50	1.133	112	100	90	82	75	69	64
L	60	1.239	123	109	98	89	82	75	70
	10	0.686	68	60	54	49	45	42	39
-	20	0.973	96	86	77	70	64	59	55
Green	30	1.186	117	104	94	85	78	72	67
(110)	40	1.372	136	121	109 121	99 110	91 101	84 93	78 87
	60	1.531 1.681	152 166	135 148	121	110 121	101 111	93 102	95
	10	0.867	86	76	69	62	57	53	49
White	20 30	1.230 1.504	122 149	108 132	97 119	89 108	81 99	75 92	70 85
(125)	40	1.504	172	152	137	108	99 114	92	85 98
	50	1.938	192	171	153	140	128	118	110
L	60	2.124	210	187	168	153	140	129	120
	10	1.372	136	121	109	99	91	84	78
1	20	1.947	193	171	154	140	128	119	110
Lime Green	30	2.381	236	209	189	171	157	145	135
(156)	40	2.752	272	242	218	198	182	168	156
1	50	3.071 3.363	304 333	270 296	243 266	221 242	203 222	187 205	174 190
	60	310.1							

Orifice		O al/Mira				MDU			
Color (Approx	PSI	Gal/Min 28-0-0	4.0	4.5	5.0	MPH 5.5	6.0	6.5	7.0
Size)	101	20-0-0	4.0	4.0	0.0	0.0	0.0	0.0	7.0
	10	0.033	2.4	2.2	1.9	1.8	1.6	1.5	1.4
	20	0.046	3.4	3.0	2.7	2.5	2.3	2.1	2.0
Pink (24)	30	0.057	4.2	3.7	3.4	3.1	2.8	2.6	2.4
	40 50	0.065	4.9 5.5	4.3 4.8	3.9 4.4	3.5 4.0	3.2 3.6	3.0 3.4	2.8
	60	0.081	6.0	5.3	4.8	4.3	4.0	3.7	3.4
	10	0.050	3.7	3.3	3.0	2.7	2.5	2.3	2.
	20	0.072	5.3	4.7	4.3	3.9	3.5	3.3	3.
Gray (30)	30 40	0.088	6.5	5.8	5.2	4.7	4.3	4.0	3.
	40 50	0.101 0.112	7.5 8.3	6.7 7.4	6.0 6.7	5.4 6.1	5.0 5.6	4.6 5.1	4.
	60	0.124	9.2	8.2	7.4	6.7	6.1	5.7	5.
	10	0.070	5.2	4.6	4.2	3.8	3.5	3.2	3.
Disale	20	0.098	7.3	6.5	5.8	5.3	4.9	4.5	4.
Black (35)	30	0.120	8.9	7.9	7.1	6.5	6.0	5.5	5.
(33)	40 50	0.139 0.156	10.3 11.6	9.2 10.3	8.3 9.3	7.5 8.4	6.9 7.7	6.3 7.1	5. 6.
	60	0.130	12.6	11.2	10.1	9.2	8.4	7.8	7.
	10	0.094	7.0	6.2	5.6	5.1	4.6	4.3	4.
	20	0.132	9.8	8.7	7.8	7.1	6.5	6.0	5.
Brown	30	0.162	12.0	10.7	9.6	8.7	8.0	7.4	6.
(41)	40	0.187	13.9	12.3	11.1	10.1	9.2	8.5	7.
	50 60	0.209	15.5 17.0	13.8 15.1	12.4 13.6	11.3 12.3	10.3 11.3	9.5 10.4	8. 9.
	00	0.220	17.0	10.1	13.0	12.0	11.5	10.4	9.
	10	0.119	8.9	7.9	7.1	6.5	5.9	5.5	5.
	20	0.169	12.6	11.2	10.0	9.1	8.4	7.7	7.
Orange	30	0.207	15.4	13.7	12.3	11.2	10.3	9.5	8.
(46)	40	0.239	17.7	15.8	14.2	12.9	11.8	10.9	10
	50 60	0.267	19.8 21.7	17.6 19.3	15.9 17.4	14.4 15.8	13.2 14.5	12.2 13.4	11. 12.
	00	0.293	£1.1	10.0		10.0	J.J	10.4	12
	10	0.149	11	10	9	8	7	7	6
	20	0.210	16	14	12	11	10	10	9
Maroon	30	0.257	19	17	15	14	13	12	11
(52)	40	0.296	22	20	18	16	15	14	13
	50	0.332	25	22	20	18	16	15	14
	60	0.363	27	24	22	20	18	17	1
	10	0.218	16	14	13	12	11	10	9
	20	0.307	23	20	18	17	15	14	13
Red (63)	30	0.376	28	25	22	20	19	17	16
	40	0.435	32	29	26	23	22	20	18
	50	0.486	36	32	29 32	26 29	24 26	22 24	21
	60	0.532	39	35	32	29	20	24	23
	10	0.351	26	23	21	19	17	16	1:
	20	0.496	37	33	29	27	25	23	21
Blue (80)	30	0.608	45	40	36	33	30	28	26
	40	0.702	52	46	42	38	35	32	30
	50 60	0.785	58 64	52 57	47	42 46	39 43	36	33
	60	0.859	04	57	51	40	40	39	30
	10	0.506	38	33	30	27	25	23	2
	20	0.715	53	47	42	39	35	33	30
Yellow	30	0.876	65	58	52	47	43	40	37
(95)	40	1.009	75	67	60	54	50	46	43
	50 60	1.133 1.239	84 92	75 82	67 74	61 67	56 61	52 57	48
	00	1.209	52	52		51			
	10	0.686	51	45	41	37	34	31	29
	20	0.973	72	64	58	53	48	44	4
Green	30	1.186	88	78	70	64	59	54	50
(110)	40	1.372	102	91	81	74	68	63	58
	50	1.531	114	101	91	83	76	70	65
	60	1.681	125	111	100	91	83	77	71
	10	0.867	64	57	52	47	43	40	37
	20	1.230	91	81	73	66	61	56	52
White	30	1.504	112	99	89	81	74	69	64
(125)	40	1.735	129	114	103	94	86	79	74
	50	1.938	144	128	115	105	96	89	82
	60	2.124	158	140	126	115	105	97	90
	10	1.372	102	91	81	74	68	63	58
l inc.	20	1.947	145	128	116	105	96	89	83
Lime Green	30	2.381	177	157	141	129	118	109	10
(156)	40	2.752	204	182	163	149	136	126	11
(50	3.071	228	203	182	166	152	140	13
	60	3.363	250	222	200	182	166	154	14

Ag Systems

SurePoint 396-001240 Tower Fertilizer System for Field-IQ™-PWM Control © 2011-2022 SurePoint Ag Systems Inc.

14

Colored Disc Orifice Chart



	Orifice		Caller				MDIT				
	Color (Approx	PSI	Gal/Min 28-0-0	4.0	4.5	5.0	MPH 5.5	6.0	6.5	7.0	
	Size)										
		10	0.033	2.2	2.0	1.8	1.6	1.5	1.4	1.3	
		20 30	0.046	3.1 3.8	2.8 3.4	2.5 3.1	2.3 2.8	2.1 2.5	1.9 2.4	1.8 2.2	
	Pink (24)	40	0.065	4.4	3.9	3.5	3.2	2.9	2.7	2.5	
•		50	0.073	5.0	4.4	4.0	3.6	3.3	3.1	2.8	
		60	0.081	5.4	4.8	4.3	4.0	3.6	3.3	3.1	
2		10	0.050	3.4	3.0	2.7	2.5	2.3	2.1	10	
		20	0.050	4.8	4.3	3.9	3.5	3.2	3.0	1.9 2.8	
2	Gray (30)	30	0.088	5.9	5.3	4.7	4.3	3.9	3.6	3.4	
	Gray (30)	40	0.101	6.8	6.1	5.4	5.0	4.5	4.2	3.9	
		50 60	0.112	7.6 8.4	6.7 7.4	6.1 6.7	5.5 6.1	5.1 5.6	4.7 5.1	4.3 4.8	11
			0.124	0.4	7.4	0.7	0.1	0.0	0.1	4.0	 (,
		10	0.070	4.7	4.2	3.8	3.4	3.1	2.9	2.7	
	Black	20	0.098	6.6	5.9	5.3	4.8	4.4	4.1	3.8	
	(35)	30 40	0.120	8.1 9.4	7.2 8.3	6.5 7.5	5.9 6.8	5.4 6.3	5.0 5.8	4.6 5.4	
	(00)	50	0.156	10.5	9.3	8.4	7.6	7.0	6.5	6.0	%
		60	0.170	11.5	10.2	9.2	8.3	7.6	7.1	6.6	
		10	0.094	6.3	5.6	5.1	4.6	4.2	3.9	3.6	
		20	0.094	8.9	5.6 7.9	5.1 7.1	4.6	4.2 5.9	5.5	5.1	
	Brown	30	0.162	10.9	9.7	8.7	8.0	7.3	6.7	6.2	
	(41)	40	0.187	12.6	11.2	10.1	9.2	8.4	7.8	7.2	
		50 60	0.209	14.1 15.4	12.5 13.7	11.3 12.3	10.3 11.2	9.4 10.3	8.7 9.5	8.1 8.8	
		00	0.220	13.4	13.7	12.0	11.2	10.5	3.5	0.0	
		10	0.119	8.1	7.2	6.5	5.9	5.4	5.0	4.6	
	0	20	0.169	11.4	10.1	9.1	8.3	7.6	7.0	6.5	I _
	Orange (46)	30 40	0.207	14.0 16.1	12.4 14.3	11.2 12.9	10.2 11.7	9.3 10.8	8.6 9.9	8.0 9.2	
	(+•)	50	0.255	18.0	16.0	14.4	13.1	12.0	11.1	10.3	
		60	0.293	19.8	17.6	15.8	14.4	13.2	12.2	11.3	
		10	0.149	10	9	8	7	7	6	6	
		20	0.149	14	13	11	10	9	9	8	C
	Maroon	30	0.257	17	15	14	13	12	11	10	
5	(52)	40	0.296	20	18	16	15	13	12	11	ח - ת
		50 60	0.332	22 24	20 22	18 20	16 18	15 16	14 15	13 14	
רו הייש הייש			0.000			20			10		1 2
		10	0.218	15	13	12	11	10	9	8	100
		20 30	0.307	21 25	18 23	17 20	15 18	14 17	13 16	12 15	'I Vi
	Red (63)	40	0.435	29	26	23	21	20	18	17	
		50	0.486	33	29	26	24	22	20	19	
		60	0.532	36	32	29	26	24	22	21	6"
		10	0.351	24	21	19	17	16	15	14	
		20	0.496	34	30	27	24	22	21	19	
	Blue (80)	30	0.608	41	36	33	30	27	25	23	
		40 50	0.702	47 53	42 47	38 42	34 39	32 35	29 33	27 30	
		60	0.859	58	52	46	42	39	36	33	
		10	0.500	24	- 00	07	05	00	04	20	
		10 20	0.506	34 48	30 43	27 39	25 35	23 32	21 30	20 28	
	Yellow	30	0.876	59	53	47	43	39	36	34	
	(95)	40	1.009	68	61	54	50	45	42	39	
		50 60	1.133 1.239	76 84	68 74	61 67	56 61	51 56	47 51	44 48	
		00	1.239	04	- 14	0/	01	50	51	40	
		10	0.686	46	41	37	34	31	28	26	
		20	0.973	66	58	53	48	44	40	38	
	Green (110)	30 40	1.186 1.372	80 93	71 82	64 74	58 67	53 62	49 57	46 53	
	(50	1.531	103	92	83	75	69	64	59	
		60	1.681	113	101	91	83	76	70	65	
		40	0.007	E0	50	47	49	20	26	22	nacin
		10 20	0.867	59 83	52 74	47 66	43 60	39 55	36 51	33 47	Ĩ
	White	30	1.504	102	90	81	74	68	62	58	1 11
	(125)	40	1.735	117	104	94	85	78	72	67	
		50	1.938	131	116	105	95	87	81	75	
		60	2.124	143	127	115	104	96	88	82	0
/		10	1.372	93	82	74	67	62	57	53	
	Lime	20	1.947	131	117	105	96	88	81	75	
	Green	30 40	2.381 2.752	161 186	143 165	129 149	117 135	107 124	99 114	92 106	%
		40	2.102	001							
I	(156)	50	3.071	207	184	166	151	138	128	118	

					1	1			Juiu	
	Orifice		0.105				MBU			
	Color (Approx	PSI	Gal/Min 28-0-0	4.0	4.5	5.0	MPH 5.5	6.0	6.5	7.0
pacing	Size)	1.01	20-0-0	4.0	4.0	0.0	0.0	0.0	0.0	1.0
		10	0.033	1.4	1.2	1.1	1.0	0.9	0.8	0.8
		20	0.046	1.9	1.7	1.5	1.4	1.3	1.2	1.1
	Pink (24)	30	0.057	2.3	2.1	1.9	1.7	1.6	1.4	1.3
		40	0.065	2.7	2.4	2.2	2.0	1.8	1.7	1.5
O		50	0.073	3.0	2.7	2.4	2.2	2.0	1.9	1.7
Ā		60	0.081	3.3	3.0	2.7	2.4	2.2	2.0	1.9
U		10	0.050	2.1	1.8	1.7	1.5	1.4	1.3	1.2
		20	0.072	3.0	2.6	2.4	2.2	2.0	1.8	1.7
	Gray (30)	30	0.088	3.6	3.2	2.9	2.6	2.4	2.2	2.1
10		40	0.101	4.2	3.7	3.3	3.0	2.8	2.6	2.4
S		50	0.112	4.6	4.1	3.7	3.4	3.1	2.9	2.6
•••		60	0.124	5.1	4.5	4.1	3.7	3.4	3.1	2.9
		10	0.070	2.9	2.6	2.3	2.1	1.9	1.8	1.6
36"		20	0.098	4.1	3.6	3.2	2.9	2.7	2.5	2.3
()	Black	30	0.120	5.0	4.4	4.0	3.6	3.3	3.1	2.8
	(35)	40	0.139	5.7	5.1	4.6	4.2	3.8	3.5	3.3
\mathbf{n}		50	0.156	6.4	5.7	5.1	4.7	4.3	4.0	3.7
		60	0.170	7.0	6.2	5.6	5.1	4.7	4.3	4.0
		10	0.094	3.9	3.4	3.1	2.8	2.6	2.4	2.2
		20	0.094	5.4	4.8	4.4	4.0	3.6	3.3	3.1
	Brown	30	0.162	6.7	5.9	5.3	4.9	4.5	4.1	3.8
	(41)	40	0.187	7.7	6.8	6.2	5.6	5.1	4.7	4.4
		50	0.209	8.6	7.7	6.9	6.3	5.7	5.3	4.9
		60	0.228	9.4	8.4	7.5	6.8	6.3	5.8	5.4
		10	0.110	4.0	A A	30	26	3.2	20	20
		10 20	0.119	4.9 7.0	4.4 6.2	3.9 5.6	3.6 5.1	3.3 4.6	3.0 4.3	2.8 4.0
pacing	Orange	30	0.109	8.5	7.6	6.8	6.2	4.0 5.7	4.3 5.3	4.0
	(46)	40	0.239	9.9	8.8	7.9	7.2	6.6	6.1	5.6
C		50	0.267	11.0	9.8	8.8	8.0	7.3	6.8	6.3
		60	0.293	12.1	10.7	9.7	8.8	8.1	7.4	6.9
		(0)			-	-				
		10	0.149	6	5	5	4	4	4	4
	Maroon	20 30	0.210	9 11	8 9	7	6 8	6 7	5	5 6
~ ~ ~	(52)	40	0.237	12	11	10	9	8	8	7
Ä	(/	50	0.332	14	12	11	10	9	8	8
D		60	0.363	15	13	12	11	10	9	9
S					-		_	-		_
		10	0.218	9	8	7	7	6	6	5
		20 30	0.307	13 16	11 14	10 12	9 11	8 10	8 10	7 9
_	Red (63)	40	0.370	18	14	14	13	10	11	10
R		50	0.486	20	18	16	15	13	12	11
10		60	0.532	22	20	18	16	15	14	13
6										
\mathbf{n}		10	0.351	14	13	12	11	10	9	8
~ /		20	0.496	20	18	16	15	14 17	13	12
	Blue (80)	30 40	0.608	25 29	22 26	20 23	18 21	17	15 18	14 17
		50	0.785	32	20	26	24	22	20	19
		60	0.859	35	32	28	26	24	22	20
		10	0.506	21	19	17	15	14	13	12
	Yellow	20	0.715	29	26	24 29	21	20 24	18 22	17 21
	(95)	30 40	0.876	36 42	32 37	33	26 30	24	22	21
	(00)	50	1.133	42	42	37	34	31	20	24
		60	1.239	51	45	41	37	34	31	29
\mathbf{O}		10	0.686	28	25	23	21	19	17	16
Ĩ	Green	20	0.973	40	36	32	29	27	25	23
	Green (110)	30 40	1.186 1.372	49 57	43 50	39 45	36 41	33 38	30 35	28 32
	(,	40 50	1.531	63	50	45 51	41	42	39	32
		60	1.681	69	62	55	50	46	43	40
U										
		10	0.867	36	32	29	26	24	22	20
V	White	20	1.230	51 62	45	41	37	34	31	29
\frown	(125)	30 40	1.504 1.735	62 72	55 64	50 57	45 52	41 48	38 44	35 41
	(50	1.938	80	71	64	58	53	49	46
Spacing		60	2.124	88	78	70	64	58	54	50
VJ										
		10	1.372	57	50	45	41	38	35	32
	Lime	20	1.947	80	71	64	58	54	49	46
	Green	30 40	2.381 2.752	98 114	87 101	79 91	71 83	65 76	60 70	56 65
36"	(156)	50	3.071	127	113	101	92	84	78	72
		60	3.363	139	123	111	101	92	85	79
\mathbf{m}										
	All application	n rates (a	allons/acres) are estir	nates bas	ed on 0-2	8-0 (10 65	lbs/gallor	n) at 70 de	grees F

15

Ag Systems

SurePoint 396-001240 Tower Fertilizer System for Field-IQ™-PWM Control © 2011-2022 SurePoint Ag Systems Inc.

Dual Metering Tube Plumbing Kits with Dual Check Valve

For more information, read <u>*Navigating the Metering Tube Maze*</u> or <u>*Metering Tube /*</u> <u>*LiquiShiftTube Charts.*</u>

SurePoint dual metering tube plumbing kits are a great way to plumb a planter to apply starter fertilizer. They'll also work on other implements when applying low rates or high rates of fertilizer.

These plumbing kits will contain everything you need to distribute fertilizer from the flowmeter outlet down to the ground application device of your choice (not included).

These instructions will show you where all the pieces go. It will provide guidance on how much

metering tube to use. There are some optional fittings included in each plumbing kit. These instructions will show you where and why you'd want to use the optional pieces.

The dual check valve assembly is a key piece in the dual metering tube design. In addition to a check valve to stop fertilizer from draining when the system is shut off, **each check** valve has an on/off valve on top of it. These on / off valves allow the operator to turn on only tube 1, only tube 2, or both tube 1 and 2. *This provides for three different application ranges*, which is especially helpful when using Black Label Zn fertilizer (or any other liquid) which has a highly variable viscosity based on temperature changes.

Dual Advantage of Dual Metering Tube Metering tube provides a larger passage-way diameter than a comparable orifice. For a 5 GPA rate on 30" rows, a size 0.046" orifice would be used. For the same rate a 0.110" meter tube that is 8' long would be used. This 8' tube with more than twice the diameter creates a fertilizer system resistant to plugging while providing excellent row to row distribution.

Components

Liquid

By using two metering tubes, the fertilizer system can handle Black Label ZN (or most other liquid solutions) and provide the proper system pressure as the fertilizer properties change due to temperature, mixtures and other factors.



Field Operation of Dual Metering Tube -Dual Check Valve System

The dual metering tube allows for three application rate ranges. Some fertilizers can have a widely variable viscosity range. Therefore, based on temperature, tank mixing and fertilizer batch, the best tube to use will change.

SurePoint recommends you start with the Green (or larger) tube ON only. This is the middle application range and is a good starting point. Conduct a test using the test speed mode to determine your system pressure. Recommended pressure is between 8 -30 PSI. If pressure is below 8 psi, some check valves may not open and row to row distribution will be uneven. If pressure is too high , pump output will decrease and you may not reach the target rate.

Start with green (or larger) tube ON, blue tube OFF:

• Pressure below 10 PSI: Turn green tube OFF and blue tube ON.

Pressure over 30 PSI: Turn BOTH tubes ON. (Other color tubes are available for different application rates.)



** Ultra Low Rate Application –For rates from 2-5 oz/min/row use a <u>12 foot</u> length of metering tube. To calculate oz/min/row: Oz/min/row = (GPA x MPH x spacing (inches)) ÷ 46.4





This is a general diagram showing the dual check valve assembly mounted on a planter toolbar. The check valve and bracket are very flexible in their mounting. The check valve can mount behind, directly over, or in front of the toolbar. The check valve can be put in the bracket facing up & down or sideways (shown). In addition the steel bracket could be rotated 90 degrees and clamp around the bar. The multiple slots in the bracket are used to mount to any tube 7x7 inches or smaller.

Sectional Plumbing Diagram with Dual Check Valves



For a <u>2 section plumbing system</u>, omit the center section and plumb similar to the outside 2 sections.



Dual Check Valve Assembly Steps

Follow these steps to mount each check valve to the steel bracket.

- 1. Screw the 3/8" MPT x 3/4" HB tee or elbow into the check valve using blue thread sealer. Orient the hose barb to run the 3/4" hose down the planter toolbar.
- 2. Insert the check valve into the "C" notch in the end of the bracket, according to how you want the check valve to be mounted on your planter. Orient the wire clips up or to the side for easiest access.
- 3. Slide the small "C" clamp bracket around the check valve to lock it in place.
- 4. Install the 1/4" carriage bolt and flange nut to secure the "C" clamp plate around the check valve.
- 5. Now, mount the check valve on the bar. Hold the check valve and long bracket assembly on the toolbar. Slide the tab on the front of the short bracket into the upper or lower notch on the long bracket.
- Slide the L bolt into the appropriate slots on the brackets for your tube size. Tighten the 1/4" flange nuts to hold the bracket in place.



Check Valve Mounting Options

The dual check valve mounting bracket is very flexible to fit many different planter configurations. Three options are shown here to illustrate some of the possibilities.





18

Connection to Keeton Seed Firmer, Rebounder Seed Covers or through thin wall stainless steel tubes

- 1. Mount the Keeton Seed Firmer or Rebounder Seed Cover.
- 2. Route the tube included in the above kit as instructed.
- 3. Attach the 1/4" tube to the 1/4" QC Y divider fitting.
- 4. Zip all tubing to the planter and row unit in as many locations as possible.

For thin wall stainless steel tubes, you can push the 1/4" black tubing all the way through the stainless steel tube so fertilizer will run directly from the tubing onto the ground.



Connection to Totally Tubular or other heavy wall Stainless Steel Tube Ground Application Devices

When using a 3/8" OD stainless steel tube to apply fertilizer to the ground, there are two options for the delivery tube plumbing. If the tube ID is less than 1/4" (tubing will not fit inside tube) this attachment method must be used. The description following is for Option 1. See bottom right picture for Option 2.

- 1. Use the 1/4" x 3/8" QC fitting shown. Push the 3/8" end onto the stainless steel tube. (Hint: if the fitting slips off the stainless steel tube, use sandpaper or a file to roughen the end of the tube slightly)
- 2. Use a short piece of 1/4" black tubing to connect the Y fitting to the reducer fitting on the stainless steel tube.
- 3. Zip all tubing to the planter and row unit in as many locations as possible.









Trimble[®] Field-IQ[™] **Rate and Section Control Module**



SurePoint Fertilizer Systems begin at the Trimble Field-IQ Rate and Section Control Module. The picture below shows this control module. You will need to purchase this module from your Trimble dealer. You will also need to purchase an unlock code for your Trimble display to enable rate control functions.

The rate controller has two harness connections. The first is the connection to the Trimble wiring harness (18-pin) that connects to the in-cab display. The second (30-pin) is where the SurePoint Fertilizer System harnesses begin. The following pages show system diagrams for single section, 2-6 section and 7-12 section configurations. Detailed harness drawings follow for information and troubleshooting.

Instructions for setting up the Field-IQ on the in cab display are in Section F. Detailed screen shots of the TMX-2050, FmX & FM-1000 and displays are included showing exactly what settings are required and recommended for SurePoint Fertilizer Systems.



© 2011-2022 SurePoint Ag Systems Inc.

Ag Systems

Trimble® Field-IQ[™] Rate and Section Control Module



This chart shows you the output functions by pin location on the Trimble Rate and Section Control Module. Use this information to verify if the Trimble system is providing the correct output. If the module is not providing the correct output, contact your Trimble dealer to repair the problem. Also review any applicable settings on the display to verify the system is properly set up.

Check with your Trimble dealer or online for the current software and firmware for your display and Field -IQ module.



Common Troubleshooting:

PWM Signal to Pump: Pins E1 to E2 on the 30-pin connector should have 3-12 volts to turn pump on. Use manual mode to increase signal. Should get up to 12 volts after holding increase button.

Flowmeter Tap Test: Pins C2 and C3 on the 30-pin connector are Flow Signal and Ground. If no flow is registering on the display, you can tap between these two pins with a short wire. This produces a pulse. The display should indicate a flow when this is done rapidly. (*Note: To help register flow for the tap test, change the flowmeter calibration to 1, so it will show a flow with fewer taps. Be sure to reset the flow cal to the proper number after the test.*)

See the drawing of harness 213-02-3764Y2 on page 28 for all pin locations on the 30-pin connector.



Trimble® Field-IQ[™] PWM Wiring Schematic Single Section for Tower Electric Pump Liquid Application







Trimble® Field-IQ[™] PWM Wiring Schematic Up to 12 Sections for Tower Electric Pump **Liquid Application**



* It is possible to connect 2 pressure sensors to the Trimble display using the Surepoint xxxxxXY2 harnesses with Pressure 1 and Pressure 2 connections.



Wiring & Elec

24

40 Amp PWM EPD (Pulse Width Modulated Electric Pump Driver) Item Number: 205-19024 with Anderson connectors (replaces 205-18385 with 480 MP connectors)

Wiring & Elec.

The Electric Pump Driver powers 1 or 2 electric pumps by providing a pulse width modulated signal to control pump speed. It needs to have a power connection and wiring capable of carrying up to 40 amps of current. It must be connected directly to the tractor battery. SurePoint recommends 8 gauge wire (or heavier) if extending harnesses in the field.

PWM Connection on pump harness

Beginning in late 2015, these four connectors are Anderson connectors

Plug in 1 pump directly OR plug in 2 pumps with "Y" cable PN 205-3116Y1.

Troubleshooting Tip: -

If the pumps won't run, connect the power and pump connector directly together to give pumps full 12 volts directly from battery. This will tell you if the pumps are the problem or if something else is wrong. The pumps will be running at full speed, so don't leave them connected this way for lona.

Use the test connector on the line from the battery to test the voltage under load.

The most common issue with the EPD will be a low voltage condition (under load) delivered to the EPD from the battery. Voltage drop occurs anytime current is moved through a wire. A low-voltage (12 v) system with long runs (60-80 feet) may have unacceptable voltage drops if any part of the system is weak or the load is high. This could be bad (corroded, weak, loose or burnt) connectors (at the battery. at the hitch, and at the EPD), too small of wire used (smaller wire equals more voltage drop), low source voltage, and heavy load. Any or all of these may contribute to a low voltage condition under load that may shut down the processor in the EPD module. This will be indicated by 4 quick flashes of the red light, followed by a short pause. Unplug the power-in connector to reset the EPD.



205-19024

EPD Power Harness PN 205-3118Y1 (20 feet) connect to tractor battery. This is 6 AWG wire.

40 Amp in-line fuse

Use EPD Power Harness Extensions as needed

(These have Ander	rson Connedtors)	Wire Size
206-02-3120Y1	1' Extension	10 gauge
206-02-3121Y1	5' Extension	10 gauge
206-02-3122Y1	10' Extension	8 gauge
206-02-3123Y1	20' Extension	8 gauge
206-02-3124Y1	30' Extension	30' and longer—6 gauge
206-02-3125Y1	40' Extension	
206-02-3126Y1	50' Extension	
206-02-3127Y1	60' Extension	
206-02-3128Y1	Power Switch-8 AWG	

SurePoint recommends a single long extension harness as multiple connectors will reduce voltage, increase current and hurt performance of your electric pump system.



Ag Systems

Implement Lift Switch for Field-IQTM (Mercury Run/Hold Switch)

The Mercury Run/Hold Switch turns liquid application on and off automatically when the implement is raised or lowered. The switch is mounted on a component that rotates when the implement is raised and lowered. The switch is attached to a magnetic base for easy mounting to any metal part of your tractor hitch or implement.

For mounted 3-point equipment:

- Mount the switch on the tractor 3 point arms.
- See the pictures below for switch orientation in run and hold positions.
- Connect the switch to the Run/Hold Switch connector on Harness 213-03-3764Y2.

For hitch drawn implements:

- Mount the switch on a wheel frame that rotates as it lifts the wheels up and down to raise and lower the implement.
- See the pictures below for switch orientation in run and hold positions.

Implement Lift Setup

Edit settings by pressing each one individually.

Press the green accept button to

FM-750 or CFX-750

Connect the switch to the Run/Hold Switch connector on Harness 213-02-• 3764Y2.

See page 52 of this manual or the User Guide for your Fm X Display to set up the Implement Lift Switch. --

Run/Hold Switch Logic

How to Adjust:

If your controller is turning off product application before or after you want, tilt the switch. If it turns off after you want when lifting the implement, tip more to the HOLD position. If product application should begin sooner when you lower the implement, tip more to the RUN position.

You can adjust the switch by moving the magnet or by loosening the screw and rotating the mercury switch.

O 0 \cap O Switch Open tch Closed Magnet to attach to metal surface. RUN Position with Wires UP **HOLD Position with Wires DOWN**

How to Test:

SurePoint

Ag Systems

To test the run / hold mercury switch you will need a volt meter. Set the meter to test continuity (or ohms). With the wires down, you should have continuity between the two pins in the connector. With the wires up, the switch should be open (no continuity).



Implement Lift Enable Yes

Number of Switches

Min Changed Switches



Calibrating the implement lift

1. From the Field-IQ Calibration

screen, select the Implement Lift

2. Raise the implement and then tap

3. Lower the implement and then

4. Tap OK to return to the Field-IQ

switch Fm X or FM-1000

option.

Next.

tap Next.

Calibration screen.



Wiring & Elec.

Trimble Field-IQ Wiring Schematics

Your Field-IQ system may have one of the following two sets of harnesses. The first set is being introduced during the 2018 season. The second set is the legacy set that has been used for several years.

New Trimble Field-IQ harnesses for the 2018 season:

Adapter Harness

213-02-3764Y2 Field-IQ Adapter harness with 12-pin Product and 14-pin Section connectors

Pump Harness

207-4189Y1 12-pin Final Cable for Tower with 1 or 2 Section Valves (PWM, Flow, Pressure, Sect 1 and 2)

Or

207-4190Y1 12-pin Final Cable for SurePoint PumpRight Liquid System (PWM, Flow, Pressure)

(Note: 207-3461Y2 and 207-3462Y2 will NOT work on the Trimble system. 207-3461Y2 and 207-3462Y2 have Yellow and Black on the PWM connector. 207-4190Y1 and 207-4189Y1 have Yellow and Green.)

Section Harness (if needed)

207-3463Y1 14-pin 6-section Final Cable

Trimble Field-IQ Legacy Harnesses

Adapter Harness

201-215464Y4 Trimble Field-IQ Rate & Section Control Module to twin 16-pin AMP connectors

Pump Harness

207-215223Y2 **PWM Pump Cable**

Section Harness

- 207-215466Y2 16-pin 6-Section Harness
- 207-215467Y2 16-pin 12-Section Harness

















Floating Ball Flow Indicators

Flow Indicators are extremely flexible and can be mounted in hundreds of different configurations on various types of liquid application equipment. This page is to give you some ideas and let you customize the installation for what works best on your equipment.

16 Row Split 6 - 4 - 6

This configuration works well on a 16 row front fold planter. Each flow indicator manifold is shown fed by a cross in a single section installation. Each manifold could be fed by a section valve if desired.



From Flowmeter Outlet

Installation

Overview

12 Row

Split 3 - 3 - 3 - 3 Shown here is a 12 row with four 3 row sections controlled by four section values. Note each 6 row T-Bracket can hold two separate 3 row manifolds.

A 4 section 24 row could be similar with four 6 row manifolds on two large T-Brackets.

12 Row Dual Product

Product 1 Split 4 - 4 - 4 / Product 2 Split 4 - 4 - 4 In this case each manifold would be fed by a section valve. There would be 6 total section valves (3 sections X 2 products). Most often one set (top) of flow indicators would be Full Flow for high rate fertilizer and 2nd set (bottom) would be Low Flow for starter.



NOTE: Another option is the flange can face forward so the T-Bracket could be mounted on the front side of a bar.

General Plumbing Guidelines





Tower 110 & 200 Mounting Options

Tower Basic Mounting Bracket Item Number: 511-1007 (8x16 hitch) 511-1008 (8x12 hitch)

This kit includes a bracket to mount to the top side of a bar or hitch and mount the tower directly over that bar. It is often used on front fold planter hitches. Ubolts to mount to two common hitch sizes are included in the kits as labeled above.



Tower Offset Mounting Bracket Item Number 511-1010

The Tower is available as a stand alone item. This kit includes a bracket to mount to the top side of a bar and hold the Tower . U-bolts are NOT INCLUDED. They must be ordered separately based on mounting bar size. Multiple slots allow the Tower to be mounted away from or directly over the bar.

Tractor Front Mount Elliptical Cradle Tower Mounting Bracket

Item Number 511-1009

Mounts a Tower directly to the front of tractor front mount 200 & 300 gallon elliptical tank cradles. This bracket will mount the back of the tower just over 4 1/2" forward of the flat bracket mounting face. When using a tractor mounted tank, SurePoint recommends mounting the Tower near the tank, not back on the implement. Electric pumps work better to push the liquid than to suck the liquid a long distance into the pump inlet.



Installation

Overview

500 Gallon Elliptical Cradle Tower Mounting Bracket Item Number 526-10-200500

Mounts a Tower directly to the side of the SurePoint 500 gallon elliptical tank cradle. This bracket will mount the back of the tower just over 9" forward of the flat bracket mounting face.

33



Ag Systems
Accelerator with Tower 200 Pump Panel

The Accelerator is a completely assembled and tested fertilizer system. It has a 55, 110, or 155 gallon tank resting in a custom molded tank base that doubles as a rinse water tank. This bolts to a steel frame with eighteen 5/8" mounting slots for flexible mounting to fit many situations. The Tower 200 is often used with the accelerator to work with the rinse tank base.

Dimensions:

Ag Systems

55 Gallon: 27" W x 54" L x 36" T 110 Gallon: 28" W x 72" L x 36" T 155 Gallon: 28" W x 72" L x 46" T



Accelerator Z Mount Kit (fits 5" to 7" wide bars, included bolts fit 7" tall bar) Item Number 526-01-100300



This mount kit includes two welded brackets to mount any of the 3 sizes of accelerator tanks above and offset from the 7x7 planter toolbar as shown.





Tower 110 Plumbing Overview & Valve Operation



Do I need recirculation flow?

Recirculation flow allows the pump(s) to run faster than if the total pump flow was applied to the ground. <u>This</u> is helpful when operating at very low flow rates. On a Tower 110 equipped with two 5.3 GPM pumps, you likely will NOT open the recirculation valve if applying over 1.5 GPM to the ground.

How to use the Recirculation Adjust Valve:

Follow these steps to set the agitation adjust valve after your system is primed and tested:

1.On the Trimble display set a manual speed in speed input settings. Enter your field operating speed and rate. Turn your master switch on. The system will now operate at your Target Rate and Test Speed.

2.Start with the recirculation adjust valve completely closed and note the slow pump speed (by pump noise).

3.Open the agitate adjust valve slowly and note the increased pump speed and noise. The system is applying the same amount to the ground, the pumps are now running faster due to more recirculation flow.

4.Set the valve to somewhere in the middle based on visual observation of agitation flow needed.

5.On your Trimble display, verify the system has locked on to application rate at your agitation valve setting.

Troubleshooting:

•If the system can not reach your Target rate, you need to close the agitation adjust valve some.

•If the system is applying a rate higher than you want and will not lock on rate, you need to open the agitation adjust valve some. Also check for a Minimum Flow setting or PWM Low Limit that may not let pump go slow.

•If the rate is still fluctuating around your target and you have a two pump system, unplug one pump. <u>At low</u> flows, one pump may deliver the needed rate and produce a more stable flow.

What if my product needs agitation?

• Tower Electric Pump systems can provide minimal agitation. On the Tower 110, simply remove the tee located below the recirculation valve. Connect the main hose from product tank to the filter and connect the tank agitation hose to the recirculation valve. Agitation will reduce the amount available to the rows.







Tower 200 Valve Operation

System Mode Valve: This valve selects if you will apply to the rows. Valve must be in the up position for field operation. Move down to Agitate Only for tank mixing prior to field operations.

Tank Selection Valve: This valve selects if product is pulled from the fertilizer tank or rinse tank. For field operation_the valve must be up. Move down to Rinse Tank to flush fertilizer system.





Agitation Adjust Valve: RECIRCULATION KNOB This valve adjusts how much flow returns to the tank while working in the field. Normally closed. If needed, start with a quarter turn.

Agitation On/Off Valve: This valve will shut off agitation flow without the need to move the agitation adjust valve. This valve must be closed when rinsing the system with product still in the fertilizer tank. If not closed, the rinse water will be injected into the fertilizer tank through the agitation line.

How to use the Agitation Adjust Valve:

Agitation or recirculation flow serves two purposes. First, it mixes products that will separate. Second, it allows the pump(s) to run faster than if the total pump flow was applied to the ground. The pump(s) will become difficult to control if they are operated at the slowest speed possible. By circulating product back to tank, the pump(s) will run faster, producing a more stable flow.

Follow these steps to set the agitation adjust valve after your system is primed and tested:

1. On the Trimble display set a manual speed in speed input settings. Enter your field operating speed and rate. Turn your master switch on. The system will now operate at your Target Rate and Test Speed.

- 2. Open the Agitation On/Off valve.
- 3. Start with the recirculation adjust valve completely closed and note the slow pump speed (by pump noise).

4. Open the agitate adjust valve (Recirculation Knob) slowly (start with a quarter turn) and note the increased pump speed and noise. The system is applying the same amount to the ground, the pumps are now running faster due to more recirculation flow.

5.Set the valve to somewhere in the middle based on visual observation of agitation flow needed. (A quarter to a half turn is often sufficient recirculation to speed the pump up slightly.)

6. On your Trimble display, verify the system has locked on to application rate at your agitation valve setting.

Troubleshooting:

- If the system cannot reach your target, you need to close the agitation adjust valve some.
- If the system is applying a rate higher than you want and will not lock on rate, you need to open the agitation adjust valve some. Be sure there is not a Minimum Flow Setting or Low PWM Limit.
- If the rate is still fluctuating around your target and you have a two pump system, unplug one pump. At low flows, one pump may deliver the needed rate and produce a more stable flow.



Home Screen > System Information Home FM-1000[™]Integrated Display Configuration Setup - Diagnostics Run Screen Support System Information Camera

System Information

From the HOME screen, you can select 3 tabs; Support, System Information or Camera. The System **Information** tab is shown above. This will show what Trimble components are properly connected to your display. If your fertilizer system quits functioning, first check that the Field-IQ Rate & Section Control Module is still recognized on the display. If not, inspect the Trimble wiring harness connections or consult vour Trimble dealer.

Connecting to EZ-Steer...

GPS Receiver: Internal

Omni* ID: 120-0013077

Rate & Section Controllers: 1 RSCM sn [5037583914]

Version: 11.10.004.4 hw:E

FW Build date: Wed Dec 21 2016

Step 0 of 15

Unknown

Field-IQ

CFX-750 and FM750 Users

App Build: 10.13.101340 (Apr 13 2017

Serial Number: 5038585094 Part Number: 93110-20-00

Internal temperature: 79.2 °F

USB: 2.3GB available

Internal Storage: 1.8GB available

Demo passcode expired or invalid. Operational Hours: 7156.2 since Dec 2012

Install: gemini_abs_0016/FS_0067 HW Ver G

00:02)

The SurePoint Tower system will also work with Field-IQ on the 750 displays. All the information in this manual is applicable to the 750 except for screen shots shown in Section F. Setup & Operation. The calibration and setup values in section F DO apply to the 750. However, the 750 has a completely different screen layout and menu structure that is not shown in this manual. Use your Trimble manual to navigate, then enter the appropriate numbers from the SurePoint manual.

Use your Trimble FmX® Integrated Display USER GUIDE (Chapter 10 Field-IQ Plugin) or CFX-750[™] Display USER GUIDE (Chapter 5– Field IQ System) for further configuration instructions.

TMX-2050 Users

The SurePoint system works well with the TMX-2050 running the FMX Plus Application. Some screens look a little different, but setup is similar to the Field-IQ setup for the regular FmX.

The TMX-2050 and latest versions of the FmX software use the Proportional Gain setting instead of the Integral Gain. Using the AutoTuning procedure should give values that work. The screenshots on the following pages show what a typical setup might look like. Your setup may vary from what is shown.

© 2011-2022 SurePoint Ag Systems Inc.

The TMX-2050 User Guide has complete information on the setup and operation of this display. Chapter 6 > Implements > see Application control Chapter 10 > Operations > Field-IQ system operations Chapter 11 > Diagnostics / Troubleshooting

Setup & Operation

Check with your Trimble

dealer for the latest soft-

ware/firmware updates.

FmX & FM-1000 Home Screen > Support



Firmware Upgrade

Hardware Firmware FIQ Rate Section Module 3 20 Display Field-IQ FIQ Rate Section FIO Rate Section Module 4 11 FIQ Rate Section Module 4 13

Field-IQ Diagnostics

Operations Hardware Sensor Row Monitor								
Controller	S/N	Position	Version	Status	Details	Auth	Tx/Rx	Errors (0
Rate and Section Control Module	5607501428	n/a	4.13	Master is off		Yes	98 / 99	
Rate and Section Control Module	5315512570	n/a		Not detected		No	0 / 0	
Master Switch Box	5537500244	n/a	3.06	Connected		Yes	98 / 99	



Ag Systems

396-001240 Tower Fertilizer System for Field-IQ™-PWM Control 39 © 2011-2022 SurePoint Ag Systems Inc.

TMX-2050 with FmX Plus > Home Screen > System Information



On the TMX-2050 Startup screen, press the FmX Plus icon to start the FmX Plus app.





TMX-2050 with FmX Plus > Home Screen >

Open Field

Ag Systems

Configuration S	election		
Display	System Language: English Units: Feet and Inches Keyboard: QWERTY	Switch	Edit
Vehicle	Vehicle	Switch	Edit
Implement	New implement 20' 0" swath width 20' 0" application width 2 sections	Switch	Edit
	8 rows		ок
Field Selection			2
Client	SFA	•	New
Farm	SFA	•	New
Field	North 40	•	New
Event	t2	•	New
	Event Attributes		
Selected Implement	New implement 20' 0" swath width 20' 0" application width 2 sections 8 rows		ЭК
			*
		Tank: Starter Target 4.00 ga Actual 0.00 ga Tank Level 186.5 ga Hitch: 28 Target n/a Actual 0.00 ga Tank Level 400.0 ga	I/a
SurePoint 396-001240	Tower Fertilizer System for Field-IQ™-PWM Control © 2011-2022 SurePoint Ag Systems Inc.	41	Revised 07/05/2022

TMX-2050 with FmX Plus > Home Screen >



© 2011-2022 SurePoint Ag Systems Inc.

Ag Systems

Implement Setup

Implement Setup is where you set the information for the implement you are using. Some of these settings affect the guidance control. However, if using auto section shutoff, these settings will determine when each section valve shuts off.

Measure your implement carefully and consult your Trimble dealer or the Trimble FmX Integrated Display User Guide (Chapter 10) for additional assistance with the Implement Setup section.





Setup & Operation

- 1. From the Home Screen select the wrenches to go the Configuration screen.
- The Configuration screen below will appear. Choose Implement. If the Setup button is locked, shown by a padlock next to it, Push Setup (to edit the Implement that is shown) or Switch Configuration (to set up a new Implement or to switch to an Implement previously entered), then enter "2009".
- You will be ready to edit the Implement Setup or to enter a New Implement Setup.

From this screen, either select a previously entered Implement or select **New** to set up a new implement.



Implement Setup (continued)



Select Field-IQ as the Active Plugin.



If entering a New Implement, type in a name for the Implement, and then press OK.



For Implement Type, select **Planting** (if setting up a planter to apply fertilizer) or the appropriate Implement Type.

Edit the Layout of the Planter (or other Implement) as needed.



44

Enter the appropriate measurements for the Implement. On the **Next** screen, enter the **Geometry** measurements requested.

You must review and configure each tab before

continuing



Implement Setup

Planting

Edit

Operations

Layout

Implement Type

Cancel

? 💿

Implement Setup (continued)

implement Oetup (continued)	
Implement Setup Implement Type Measurements Geometry Overlap Switcher Infill Boundary Outer	Select either "Outer" or "Inner" for the Infill Boundary on the Overlap Tab. Outer uses the field boundary as the infill boundary. Inner: When running a Headland setting, this moves the boundary to the inside of the last headland pass.
	ement Setup Measurements Geometry Overlap Switches Implement Lift Setup Auxiliary Master Switch Disabled
Add/Edit Implement Lift Sensor	



If using an Implement Lift Switch, change the Status to **On**. Enter the number of switches and the minimum number of switches that need to change. You will need to Calibrate the Implement Lift Switch later on by going to Field IQ -Configuration - Implement Lift Switch (see page 25 and page 50.)

When you return to the beginning screen, select **Save Configuration**.

The Implement should be set up.





Configuration - Field-IQ[™] Setup

In the Setup & Calibrate menus you will set the Trimble Field-IQ to work properly with the SurePoint Fertilizer System. Carefully follow these steps to first make the proper settings. Then, run the tests shown to verify your fertilizer system is ready to go to the field.





- 1. From the Home Screen access the Configuration screen (wrenches).
- The Configuration screen below will appear. Choose Field-IQ. If the Setup & Calibrate buttons are locked, shown by a padlock next to them, Push Setup, then enter "2009".
- 3. After entering the code, the locks will disappear. Push Setup to proceed to the next steps.

(If the Calibrate and Diagnostics buttons are grayed out, you probably need to close a Field.)



Ag Systems

396-001240 Tower Fertilizer System for Field-IQ[™]-PWM Control © 2011-2022 SurePoint Ag Systems Inc.

46

Revised 07/05/2022



Select one of the Available Materials or press Add to add a new material.

Press **Edit** to change any of the parameters of the Material.

I	Naterial Details: 10-34-0	2
	Material Alarms Operation Advanced	
		1
	Material Type 🗸 Liquid 🗾 Target Rate 1 8.00 gal/a	
	Material Name 10-34-0 Target Rate 2 12.00 gal/a	
	Rate Increment 1.00 gal/a	
	Manual Rate Increment 100 %	
	Minimum Rate 0.00 gal/a	
	Maximum Rate 30.00 gal/a	

These parameters may be adjusted as desired.

Jump Start Speed is the speed the system will ramp up to when the operator pushes the Jump Start button on the Master Switch Box. 3.0-5.0 mph is a good setting for this. **Jump Start Timeout** allows the Jump Start Speed to run for a specified amount of time.

Apply Latency to Boundary: Set as needed so the system begins applying when needed.

SurePoint recommends setting the **Rate Snapping** to **On**. This will smooth out the rate fluctuation seen on the screen. If you are within the rate smoothing range, the applied rate will just show your target rate, and not small deviations from the target rate.

Material Setup



To set up the Material, press **Material Setup**.



Set Target Rate 1 & Target Rate 2 as desired.

Rate Increment increases or decreases Rate 1 or Rate 2 by this amount each time you press the Rate Adjustment Switch on the Master Switch Box.

Manual Rate Increment works when the Rate Switch is in the Manual Position. This number controls the speed at which the valve increases or decreases when you press the Rate Adjustment Switch on the Master Switch Box.

Minimum Rate is typically set at 0.

Maximum Rate is set at something higher than the maximum rate that will be applied.

Material Deta	ails: 10-34-0			2 🔍
Material Alarr	ms Operation	Advance	ed	
	Jump Star	t Speed	5.00 mph	
	Jump Start Timeout		0.00 s	
	Shutoff Speed		0.36 mph	
	Minimum Override	e Speed	0.00 mph	
	Apply Latency to Bo	oundary	No	
	Rate S	napping	On 💌	



Trimble® Field-IQ[™] Setup for FmX[®] or FM-1000[™] (continued)



If this is the first time to do Control Setup, there will be no Locations entered. In that case, press Add and enter the information for a location.

If there is a location and material set up, you can select and/or edit it.



From this screen, you can add a Location Name such as Front Tank, Rear Tank, etc..

If desired, you can set up the **Bin/Tank Setup** to allow the system to track how much material is left in the tank. (See screenshot on next page)

Control Setup 0 Location Material Module SN Status RSCM 5037583914 Connected Liquid Add Edit Delete

Control Setup

Select an Available Material.





Revised 07/05/2022

Setup &

Operation





Optional. If desired, enter the information here to let the controller monitor how much material is left.

Section Control

See the FmX Integrated Display User Guide, beginning on page 10-25, for more information.

> Press Setup next to Section Control Module Location.

_			
	SF		? 返
	Material	Layout Section Control Rate Control Sensors	
4			
-		Section Control On	
		Section Control Module Location	
		Section Control Setup	



- 1. Set the Number of Modules in your system.
- 2. Select the Module Serial Number.
- 3. Set the number of Sections for your system.
- 4. Press Section Widths.



Section Widths Section Control Setup (cont.)





1. Set Section Control Type to Boom Valve.

Section Control

Section Control

Location

Setup

Setup

Section Control Module

- 2. Set Off When Stopped to Yes.
- 3. Press Latency.





~	SF					
	Material	Layout	Section Control	Rate Control	Sensors	
	Rate Control On					
		Rate Cor	Setup			
			Drive Setup	Setup		
			Number of Nozzles		16	
		I	No/Low Flow Timeout		5 s	

- 1. Set the correct information on this screen.
- 2. Press OK.
- 3. The next screen should look like the screen above. On **Drive Setup**, press **Setup**.

C	Drive Setup
	Valve Setup Feedback Setup
	×
	Valve Type PWM
	Plumbing Inline
	Valve Behavior When Sections Close
	Auxiliary Valve Disabled
	Pump Disarming Switch Disabled

Set the Feedback Setup screen as shown. Flowmeter Calibration = 3000.

This flowmeter calibration will work with the flowmeter that has the blue label or orange label on the PumpRight System.

Earlier flowmeters have a white label with black text and have different calibration numbers.

Rate Control Setup

Setup & Operation

See the FmX Integrated Display User Guide, beginning on page 10 -32, for more information.

- 1. Select the Rate Control tab at the top.
- 2. Set Rate Control to On.
- 3. Set Number of Nozzles number or rows).
- 4. Set **No/Low Flow Timeout** to 45 s for troubleshooting so the system does not shut off too quickly.
- 5. Press Setup next to Rate Control Module Location.

Rate Control Module Setup		?
Number of Drives 1		
		-
Module	5037583914	
Width	40' 0.0"	

Set the Valve Setup as shown. ValveType: PWM Valve Behavior When Sections Closed: Close Auxiliary Valve: Disabled Pump Disarming Switch: Disabled

(Optional: If using an Aux/Dump valve to keep the pump running when application stops so the system will resume applying at the Target Rate immediately upon restart, set Auxiliary Valve to Dump, then set Valve Behavior When Sections Closed to either Lock in Last Position or Lock at Minimum. This setup requires section valves with an additional dump valve plumbed to return flow to the tank when application stops.)

Drive Setup						
Valve Setup Feedback Setup						
Min Flow: Use these settings for your flowmeter.						
0.13—2.6 GPM 0.1GPM 0.3—5.0 GPM 0.2 GPM						
Flow Meter Type Other						
Flowmeter Calibration 3000 pul/gal						
Min Flow 0.0 gal/min						





Pressure Calibration

SurePoint

Ag Systems

Transducer - Module 5037583914

396-001240Tower Fertilizer System for Field-IQ™-PWM Control52© 2011-2022SurePoint Ag Systems Inc.

screen.

Field-IQ Calibration	Field-IQ Calibration Setup &
	Operation
Rate and Section Control Module 5037583914 Trive Calibration Flow Calibration	Select Field-IQ - Calibrate on the Calibration screen. This brings up the screen on the left. Select Drive Calibration.
Set the Maximum Flow rate at 5 gal/ min. Select Next. Follow the screen instructions to run the Auto Tuning Procedure. After the Auto Tuning Procedure you can press Next at the bottom of the Auto-Tuning screen to go to the Drive Settings screen.	Field-IQ Drive Calibration Image: Coloradia and the system of the sy
Field-IQ Drive Calibration Info Drive Limits Auto-Tuning Drive Settings Info Turn the Master Switch on and vary between rates to ensure your system performs at the level you require. Target Speed 5.00 mph Target Speed 5.00 mph Proportional Gain 25 Target Rate 4.00 gal/a R1 Minimum Response 20.0 Applied Rate 0.00 gal/a Allowable Error 2.0 Master Switch Off Boost (Feed Forward) Off	Mow its time to run the drive to determine if it can run within the required speed and rate parameters. Turn the Master Switch On to start the Auto-calibration Process. When the progress bar has completed, turn the Master Switch Off and Press Next. If at any time you need to shut down the drive, switch the master switch to the off position and adjust the rate and speed parameters on the previous page as necessary. All rows and sections will be commanded fully open during this process. Master Switch Off Current Flow 0.00 gal/min Select the Advanced Parameters button to bring up the Advanced Tuning screen (shown below). Here you will enter the numbers for the system. Target Speed: Enter a typical operating speed. Upper PWM Limit: Make sure this is set to 100. If Auto
Advanced Paramete	-Tuning has been used, the Trimble control will set it at a lower number that will limit the upper range of your

pump.

Lower PWM Limit: 0

Recommended Settings for Tower Electric Pump for FmX:

Proportional Gain: 25 (20-30). If the gain is set too high, the system will surge above and below the desired flow. Lower the gain to achieve steady pump operation. Raise the gain if the system is slow to adjust to speed and rate changes.

Minimum Response: 10-20% This helps the pump start faster as well as react quicker to changes.. Raise it to get to Target Rate faster when starting. Lower it if system overshoots Target Rate when starting or when going across the field.

Allowable Error: From 1% to 2%

Process Gain: 0.10

Smoothing Factor: 5

Older software versions use Integral Gain instead of Proportional Gain. In that case, use the Proportional Gain numbers shown above for the Integral Gain. **Field-IQ Drive Calibration** ?) Advanced Flow Advanced PWM Advanced Pressure Turn the Master Switch on and vary between rates to ensure your system performs at the level you require 5.00 mph Target Speed Proportional Gain 25 0.00 Target Rate 4.00 gal/a R1 Integral Gain Applied Rate 0.00 gal/a Differential Gain 0.0000 20.0 % Master Switch Off Minimum Response Integrator Upper PWM 100.00 Hz Allowable Error 2.0 % Limi Integrator Lower PWM 0.100000 0.00 Hz Process Gain Limit Smoothing Factor 100.00 Hz 10.00 % Comparator Limit (Flow Filter Time Constant) 655.00 Hz 0.00 Ramp Limit Pre Position Open Boost (Feed Forward) Off Pre Position Stop 0.00 \mathbf{T}



Field-IQ Drive Calibration: Advanced PWM

Field-IQ Drive Calibration 🔹 😨						
Advanced Flow Advanced PWM Advanced Pressure						
Target Speed		5.00 mph	Base PWM Frequency		100 Hz	
Target Rate	4.00 gal/a	R1	Dither Frequency		0 Hz	
Applied Rate	0.00 gal/a		Dither Amplitude		0 %	
Master Switch	Off		Dither Control	Absolute	•	
			PWM Upper Limit		100 %	
			PWM Lower Limit		10	

Advanced PWM Tab

Base PWM Frequency: 100 Dither Frequency: 0 Dither Amplitude: 0

→ Dither Control: Absolute PWM Upper Limit: 100% PWM Lower Limit: 10%

Field-IQ Calibration

	Implement Lift	Flow Calibration	
	⊟ sf: 10-34-0	Select Field-IQ - Calibrate on the Calibration screen.	
	Rate and Section Control Module 5607501428	This brings up the screen on the left. Select Flow Calibration.	
brive Calibration be		The Flow Calibration numbers may have already been set in the Drive Setup. You can verify or	
	Flow Calibration	update the settings here.	

Rate and Section Control Flow Calibration

Min Flow: Use these settings for your flowmeter. 0.13-2.6 GPM 0.1 GPM 0.3-5.0 GPM 0.2 GPM Flow Meter Type Flowmeter Calibration (Location) Min Flow The flow is the settings for your flowmeter.

Flowmeter Model (blue label or orange label)	Pulses/Gal	FPT Size	Hose Barb In kit
0.13 - 2.6 GPM	3000	3/4"	3/4"
0.3 - 5.0 GPM	3000	3/4"	3/4"
0.08 - 1.6 GPM	22700	3/4"	3/4"

The flowmeter calibration number (pulses/gal) is printed on the serial number sticker on the side of the flowmeter.

Earlier model flowmeters (meters with white labels with black text) have different calibration numbers. See the documentation for those meters to find the calibration numbers or check on the serial number sticker.



Setup & Operation

Initial Operation Instructions

SurePoint recommends you perform these exact steps with water to verify system is correctly installed and ready for field use.



OK

Configuration		
System [System]	Setup	From the Configuration Screen, select Field-IQ , then Diagnostics . (If the Diagnostics tab is grayed out, you
EZ-Steer [New Vehicle]	Calibrate	probably need to close a Field.)
GPS Receiver	Diagnostics	Field-IQ Diagnostics
Implement [SF]	Save Config	Control Mode Manual Location ef: SF
Field-IQ	Switch Config	Current Flow 2.37 gal/min Control Speed 5.0 mph Target Rate 8.00 gal/a - + Master Switch On
1 Description of the star start to Orac edite started		Speed 5.0 mph - +

- 1. Press the + next to Speed to simulate a Speed signal.
- 2. Turn the Field-IQ master switch (#5) on (see picture below).
- 3. Push each section valve button and verify each valve is working.
- 4. Turn Switch #2 to Manual and open the section valves. Use switch #1 to increase flow. Does "Current Flow" display a flow rate? Is it stable after the system is primed? Do increase & decrease buttons increase & decrease flow?

1 2

View Error Log

- 5. Move switch #2 to Rate 1 and set speed to your typical field speed.
- 6. The system should begin to pump liquid now in automatic control mode. Is the flow in GPM stable? Is it applying at the correct rate? (applied rate = target rate?)
- 7. Change rate using screen buttons or switch #1 to increase/decrease rate or switch #2 to go to Rate 2. Does applied rate change to equal target?

(**Aggressiveness** can be set anywhere from 100% to 150% to make quicker adjustments to rate changes.)

- 8. Close 1 section valve, does flow decrease? Does applied rate still equal target rate?
- 9. Change speed and target rate to minimum and maximum values. Does system perform at these values? Does the system pressure seem reasonable (remember fertilizer will increase



Section Test

Aggressiveness

pressure over water)? Use "Sensor" tab at the top of page to read the pressure sensor value (if equipped).

10. Press the **Sensor** tab to see **PWM PERCENT** while the system is running. Typical operating ranges will be between 10% and 60%, possibly higher on high-rate outputs. With the control switch in Manual mode, pressing switch #1 towards (+) on the switch box should increase PWM Percent.

Running the system with water will create much lower pressure than what will occur with fertilizer. If the pressure is too low, all the check valves will not open, and some of the rows will have no flow. Increase the flow to build enough pressure to open all the check valves.



Field-IQ Diagnostics

From the **Configuration Screen**, select **Field-IQ** and then **Diagnostics**. You can test-run the system from this screen. (*If the Diagnostics tab is grayed out, you probably need* to close a Field.)



Field-IQ Diagnostics	
Operations Hardware Sensor Row Monitor Control Mode Manual Location Sf1: SF	To enable the sections, tap the numbered section tabs above each of the section icons.
Rate Switch Mode Manual	The Operations tab displays the current status of: Control Mode (Auto or Manual) Rate Switch Mode (Manual, Rate 1, or Rate 2) Master Switch (Off, On, or Jump Start)
Aggressiveness 100 % - +	This screen also allows you to manually enter values for <i>Tank Level, Target Rate,</i> and/or <i>Speed.</i>
View Error Log Section Test OK	Operate the system, and check the value shown for <i>Applied Rate</i> at various <i>Speeds</i> and <i>Target or Manual Rates</i> .
Field-IQ Diagnostics	In Manual mode, press the + or - button beside Target Rate to increase or decrease the rate.
Operations Hardware Sensor Row Monitor Control Mode Manual Location sf1: SF Rate Switch Mode Rate 2 Applied Rate 7.00 gal/a Tank Level Current Flow 2.84 gal/min Tank Level Refill Tank	You can change the Rate and/or Speed while the system is running by pressing the corresponding + or - buttons.
Control Speed 5.0 mph Target Rate 7.00 gal/a - + Master Switch On Speed 5.0 mph - + Aggressiveness 100 % - + 1 2 - - + View Error Log Section Test OK	Sensor tab: Go here while the system is running to see the PWM Percent. In manual mode, the PWM Percent should increase and decrease while the (+) and (-) button is held down on the switch box. In AUTO Mode, the PWM Percent should hold steady while the system is locked on to a rate.
Operations Hardware Sensor Row Monitor	The Sensor tab provides information on the Pressure Sensor(s) and Pump Speed (PWM Percent).
sf: SF Pressure 1 (5037583914)	To enable the pump to get to the Target Rate faster when starting, the Minimum Response (see Drive
Pressure 2 (5037583914)	0.00 psi Calibration on Pages 51-52) can be increased.
Shaft RPM RSCM (5037583914)	n/a
PWM Percent RSCM (5037583914)	37 %

Ag Systems

56

Electric Pumps Won't Run				
EPD Statu	us Lights	PWM Signal Trouble-		
Status LED	Status Description	Troubleshooting Steps Shooting		
On Steady	Power input is good and PWM input Signal is detected	No Problem, Typical operating condition. To Pump(s) Status LED- should blink once per sec- ond Power Supply (from battery)		
Steady Blink (1 hz— 1 blink/sec)	Power input is good and PWM signal is not de- tected.	 Typical 'Off' Condition. If pumps should be on: 1. Inspect wiring and connectors 2. Check voltage at PWM connector to EPD, should be 1-12 volts to turn on. 3. Check voltage on PWM wires at 37 pin connector, pins 15&16. 		
Blink once, pause, blink once, pause	Open circuit between motor output and motor.	Check harness and connectors to motor. If using two motors, plug each in separately directly to EPD (bypassing Y-harness)		
Blink twice, pause, blink twice, pause	Output short circuit de- tected.	Check motor wiring		
Three blinks, pause, three blinks, pause	Overcurrent condition	Check total loadClean cooling fins on EPD		
Four blinks, pause, four blinks, pause	Input power fault. Low voltage condition in power to EPD.	 Unplug battery power from EPD to reset. Check power cables and connections for quality. Be certain that power cable connects directly to battery and has a solid, clean connection. Test the voltage under load coming into the EPD. (See picture on page 24 for voltage test point.) Voltage may appear adequate when system is not on, but bad connectors or wiring may not carry the current needed under load.) You may be able to reduce power draw by lowering the system pressure. Typically, though, this is an indication of a cable or connector issue. 		
Five blinks, pause	Input frequency out of range.	Check PWM Settings on Rate Controller.		
Control Sig- nal LEDs (top corner)	.0.			
Light intensity varies	Off - No PWM Signal 100% brightness - Maxi- mum PWM input signal	Red light in top corner should be on when PWM signal is received (system is applying product)		

The most common issue with the EPD will be a low voltage condition (under load) delivered to the EPD from the battery. Voltage drop occurs anytime current is moved through a wire. A low-voltage (12 v) system with long runs (60-80 feet) may have unacceptable voltage drops if any part of the system is weak or the load is high. This could be bad (corroded, weak, loose or burnt) connectors (at the battery, at the hitch, and at the EPD), too small of wire used (smaller wire equals more voltage drop), low source voltage, and heavy load. Any or all of these may contribute to a low voltage condition under load that may shut down the processor in the EPD module. This will be indicated by 4 quick flashes of the red light, followed by a short pause. Unplug the power-in connector to reset the EPD. Check and correct any wiring deficiencies.



Troubleshooting / Service Tips

Always verify the controller settings. See the screenshots in Section F of the system manual and on the QuickStart setup sheet.

The pump won't run.

Electric Pump System

EPD flashing 4 times

Find the EPD module (electric pump driver—black module on Tower). Should have a steady blinking light (one blink per second) in the middle when pumps should be off. In Run mode, the center light should be steady red, the upper right should be steady red (indicates it is receiving a PWM signal). If Status LED (center light) is *flashing 4 times, then pausing*, EPD has tripped due to low voltage condition. Unplug the Power Supply to the EPD to reset. If condition persists, check Power Supply cables from battery to EPD to insure solid connections and good electrical path. Check connections at battery. Check connectors at the hitch and at the EPD. (*There should be 11.5-13 volts at the point where the EPD connects to the battery power harness, when tested under load*. This voltage may show up when there is no load, but the harnessing may not be good enough to deliver 11.5-13 volts under load.)

No Lights on EPD

1. There should be a steady blinking light in the middle of the EPD. If no light is ON, check the 40-amp fuse in the EPD harness near the battery. Use a voltmeter to verify that there is 12-13 volts at the Power Supply connector that plugs into the EPD. *If there is good voltage here, but no light on the EPD, replace the EPD module.*

Will pumps run?

- 1. Connect the two large connectors that are plugged into the bottom of the EPD to each other (bypass the module and supply 12 volts directly to pumps).
- 2. Do the pumps run? If not, check the 40 amp fuse in the EPD harness near the tractor battery. Inspect harnesses and connections. If 2 pump system, plug pumps in by themselves to check individually. If pump won't run, connect it to pickup battery with jumper cables.

Pumps run, but won't pump anything-

- 1. Are valves from tank to pump open? Is strainer clean? Close recirculation. Open air bleed valve.
- 2. Tap on pump with rubber mallet. Pour water (hot, if available) in inlet of pump. Remove outlet hose from pump.

Electric pumps only run with 12 volts direct from battery

Check to see if a PWM signal is getting to the EPD:

- 1. Connect pumps and power harness back to EPD.
- 2. Go to Diagnostics to investigate this issue.
- 3. Start Diagnostics test in manual mode, hold down "+" button for 8-10 seconds. A single tap of this button produces a very small change in signal to the valve, so you must hold it. (Look at PWM Percent on Sensor tab)
- 4. Remove PWM valve connector at EPD and check voltage. You will need 6-12 volts to turn pumps on. (PWM Duty Cycle at 100 should be 12+ volts on PWM signal)
- 5. If 6-12 volts is not present, check harnesses and review control valve type setup (should be PWM).
- 6. Go back to the 12-pin Deutsch pump connector, check PWM voltage between Pins 5 & 6.
- 7. If necessary, go back to the 30-pin outlet on the Field-IQ module. There should be PWM voltage between pins E1 and E2.

Pump starts up running full speed and won't control.

Verify that the PWM connector on the harness to the EPD has a green and yellow wire. Black and yellow will not work. Check Firmware version on Field-IQ module. Should be 4.13 or newer.

Pump runs for a while when I push the (+) button on switch box, then stops.

Verify that controller is set to PWM and not to Servo.



Troubleshooting

No Flow shown on display, but liquid is being pumped Flowmeter Tap Test

See which flowmeter connector you have



Remove red guard to reach pins. Don't break red side clips.

1 2 3

Flowmeter pinout: 3-pin MP Tower A- Signal B- 12V Power C- Ground

3-pin AMP SuperSeal 1– Ground 2– 12V Power 3– Signal

- Unplug the flowmeter. With voltmeter, check for 12 volts between Power & Ground of flowmeter connector. Should have 4-5 volts between signal and ground. If voltage is not present, inspect wiring harness and check for voltage at harness connection(s) nearer the Rate Controller (at 12-pin Deutsch connector, Power is 1, Ground is 2, Flow Signal is 3).
- 2. If 12 volts is present, then conduct a **tap test**. Go to **Setup** and change the flow cal to 1. Have a second person watch GPM on the screen while other person taps repeatedly (use a short piece of wire or a paper clip) between signal and ground pins of flowmeter connector. A flow value (gpm) should show up indicating the wiring is not damaged. (If alone, note or reset a volume counter to 0. Check for increased volume after tapping.)
- 3. If the flow showed on the display during the tap test, your wiring to that point is good. If tap test did not work, go back to the next harness connection and do a tap test there between signal and ground.
- 4. If the tap test registers flow on the display, replace flowmeter. (*Sometimes, cleaning the inside tube of the flowmeter with soapy water and a soft brush will remove a film covering the electrodes.*)
- 5. Change Flow Cal back to appropriate Flow Cal when finished with Tap Test.
- 6. SurePoint has a Speed/Flow Simulator (PN 219-01462) or a Tap Tester (212-03-3912Y1) that can be used to confirm if the wiring is good between the flowmeter and controller.

Field Verification of Flowmeter Calibration

Always verify the flow cal setting by comparing the amount actually applied in the field (from weigh tickets) with the amount shown on the display. Adjust the flow cal as needed to get less than 1% difference between the actual amount applied and the amount shown on the display.

In general:

Increase the Flow Cal number if not enough product is actually being applied. (If you want more, increase the number)

Decrease the Flow Cal number if too much product is being applied. (If you want less, decrease the number)

Formula to Adjust Flow Cal Number

(Volume shown on display) / (Volume actually applied) X flow cal number in display = new flow cal

Example: Display shows 727 gallons was applied. Weigh ticket shows 750 gallons was actually applied. Flow cal number in display was 3000. (*We applied too much, so we will decrease the flow cal.*)

727 / 750 X 3000 = 2908 (new flow cal number to set in display)

(Any adjustments to the flow cal number will only be as accurate as the measurements used in figuring it.) Do not power wash the flowmeter.

Unplug the flowmeter before welding on the implement.



Section Valve(s) will not move

- 1. Go to **Diagnostics** to investigate this issue.
- 2. Start Section Test. Check and uncheck the boxes. With the box checked the valve should turn on. The valve should be off with the box not checked.
- 3. If none of the valves are working, or if half of the valves are working, it may be a Power (or Ground) issue. The oddnumbered sections have one power source, the even-numbered sections have another power source. (See harness diagrams)
- 4. If a valve does not open, switch the connector that is plugged into that valve with a connector that is plugged into a

Pin	Function	working valve. Also, plug in the connector to the non-working valve to a valve that is working.	
А		5. Check the harness connection to the non-working valve. It is a 3-Pin Weather Pack con- nector. Check voltage pin A to Pin B. Must be 12 volts, if not, go back to the next harness	
В		connection and check the voltage there. (See harness diagrams for pins)	
С		6. If voltage is present on pins A&B of 3 pin connection to valve, then check Pin C to Pin B. This should be 12 volts when the valve is commanded on or open. This should be zero volts	

when valve is off or closed.

- 7. If signal voltage is not present to open valve, use diagrams to check at the 14-pin connector, then the 30-pin on the Field-IQ module for voltage on the proper pin for that section.
- 8. If harnesses and voltages are good, but valve still will not open, remove the actuator from the valve and see if the actuator will work when it is not connected to the valve. Use a wrench to turn the valve to be sure it is moving freely. Be sure actuator and valve are oriented correctly when you put them back together.
- 9. If constant voltage (Pins A&B) and switched voltage (Pins C&B) are present, inspect, repair or replace the valve.



This is a 3-way valve. If product will not flow when valve is ON, either move the outlet hose to the other outlet port, or remove actuator and rotate valve ball 180°, and replace actuator. Product should flow through the port closest to the Indicator light when the valve is open (green).

Pressure Sensor is not reading

- 1. Be sure the Pressure Sensor that is displayed on your screen is the same sensor that is plugged into your harness for that product.
- 2. Make sure the pins where the harness screws on to the end of the sensor have not been bent.
- 3. Be sure Pressure Sensor is set up and calibrated in the display. Unplug the pressure harness before doing this.

The calibration is 50 mv/PSI.

- 4. There should be a green LED light on the end of the pressure sensor. (may be difficult to see in daylight). The sensor needs 12 v. Check between pins B&C on the Pressure connector on the harness that connects to the pressure sensor. If there is no voltage here, check the voltage between pins 1 & 2 on the 12-pin connector labeled PUMP.
- 5. Testing Pressure Sensor Harnessing: If the pressure sensor is not reading, you can use a AA or AAA battery to test the harnessing. Connect the (-) end of the battery to pin C and the (+) end to pin A of the pressure connector. The 1.5 v should show up as 30 psi on the screen. You can check this at *Diagnostics > Sensors*.



Application Rate & Flow Troubleshooting

Application Rate Fluctuates

First, you need to determine if the fluctuation is caused by the controller sending fluctuating signals to the valve.

1. <u>Inspect & clean pump inlet strainer</u>. Strange flow rate fluctuations are very often due to an obstruction to the pump inlet. Inspect plumbing from tank to pump.

OR

- 1. Go to Diagnostics screen.
- 2. Turn the system on and watch the flow in GPM. Check PWM Percent on Sensors tab.
- 3. Is the flow steady within a very small range? For example a fluctuation from 2.3 to 2.5 GPM would be considered normal. A fluctuation from 2-3 GPM is a problem. If only a small normal fluctuation is seen, skip steps 4-8 and proceed to "Application Rate Fluctuates in Field" below.
- 4. If there is a large fluctuation, observe the system flow. Is the discharge a steady stream? Are the flow indicator balls floating steady?
- 5. If visually the flow is steady, but the display reports a fluctuation in GPM, inspect the flowmeter. See section B for flowmeter information.
- 6. If visually the flow is unsteady, the flowmeter is working correctly reporting a flow problem. Is the pump turning steady or surging? If the pump is surging, reduce the gain (or aggressiveness) setting.
- 7. Look for any type of obstruction in the pump inlet. Clean the strainer. If continually plugging the strainer, investigate fertilizer quality and necessary strainer size.

Application Rate fluctuates in field, but flow in manual mode is stable.

This problem indicates the valve calibration needs changed. The system is surging because the Rate Controller is moving the pump driver or hydraulic valve too much.

- 1. Go to Field-IQ, Calibration, Drive Calibration
- 2. Change the settings by reducing the Proportional Gain.
- 3. Run the system from the Diagnostics screen. Set up a Target speed with Auto Rate. Go to the Sensors tab and look at the PWM Percent. This should increase until the system locks onto the Target rate, and then hold steady.
- 4. Check the firmware version on the Field-IQ module. It should be 4.13 or newer. (Version 3.20 worked well in the past. This may not work with the current display software.) Display software should be current as well.

Application Rate is slow to get to the Target Rate

- 1. You may need to increase the valve calibration. Go to Field-IQ, Calibration, Drive Calibration.
- 2. Change the settings by increasing the Proportional Gain.
- 3. At Field-IQ, Diagnostics, make sure the Aggressiveness is at 100% to 150%.
- 4. If system is slow getting to Target Rate on startup after doing the steps above, set the **Minimum Response** to a higher number (see page 46). Another option to get to Target Rate quicker on startup on a system with section valves is to add an additional Aux Dump valve that is plumbed to return flow to the tank and setting the PWM valve to Lock in Last Postion (see Drive Setup on page 45).



Trouble-

shooting

Other issues

1. "My rate won't go low enough. I want 8 gpa, but it won't go less than 11."

A. Check *Field-IQ > Calibrate > Flow Calibration > Min Flow.* This can be set at 0.0 or at the low range of your flowmeter. This is *gal / min* not *gal / acre*.

0.0 or at the low range of your flowmeter. This is gai / min not gai / acre.
 B. Check Field-IQ > Calibrate > Drive Calibration > Next > Next > Drive
 Settings > Advanced Parameters > Advanced PWM > PWM Lower Limit< If

this is too high, pump will not be able to slow down. Typically, 10 is low enough, but on very low applications may need to go to 5 or less.

C. On a hydraulic pump, be sure the red manual override knob is down and locked on the hydraulic valve.

2. "I can't get up to my rate. I want 12 gpa, and I can't get more than 10 gpa."

A. How many GPM are required to hit your rate? Is this within the pump's specifications? On an electric pump, the output of the pump decreases as the pressure increases. Keep the pressure under 40 PSI on an electric system. **Is a recirculation valve open**, allowing too much liquid to recirculate? Normally, the recirculation valve should be closed. If it needs to be open, start with a quarter turn.

B. On a dual electric pump system, check each pump individually to see that each one is working at capacity.

C. **Is the strainer plugged?** If too small of a mesh strainer is being used, the fluid can gel up around the screen as the fluid is pulled through. Most SurePoint systems with metering tube and electromagnetic flowmeter can use a 20– or 30-mesh strainer.

D. Does the pump have enough hydraulic oil to hit the desired rate? If the pump is in series behind another pump or motor, the hydraulic oil to this pump may be limited. Run pump in Manual Override to see output.

E. Check *Field-IQ > Calibrate > Drive Calibration > Next > Next > Drive Settings > Advanced Parameters > Advanced PWM > PWM Upper Limit.* This should be from 80 to 100.

F. Go to **Diagnostics >** Run a test. What is PWM Percent (Sensors Tab) while the pump is running (in the field or on a manual or auto test)? 100 means the pump is being told to run at full speed.

G. Run a manual test and hold the (+) button to speed up the pump. Check GPM and PSI at different levels. Check the PWM Percent at the Sensors tab.

H. Run a test in AUTO mode with auto rate. See gal/ac, PSI, gal/min, and PWM Percent.

I. Is the flow cal correct? Is the width of the implement set correctly? Is speed reading correctly?

3. "It's pretty close to the rate, but it won't ever lock in to the rate."

Go to Setup > Material Setup > Rate Smoothing. Rate Smoothing should be ON.

Without Rate Smoothing it is normal for the system to show the rate constantly changing small amounts as you go across the field. With Rate Smoothing, if the Applied Rate is close to the Target Rate, the display does not show all the small changes.

4. How do I set the Recirculation knob?

Generally, the recirculation knob is closed. If tank agitation is necessary while applying, the recirculation hose can be plumbed back to the tank. Electric pumps do not have the capacity to do much agitation. A small amount of recirculation may be desired if the pump needs to run slowly and the output is not smooth. Start with a quarter turn of the knob (less on an electric pump). A half turn of the knob will recirculate a lot. If too much is recirculated, the pump may not be able to hit the rate to the rows. Opening recirculation will not lower the pressure required to push the desired product to the rows.





5. "My pressure is too high / too low."

The pressure will be what it is depending on how hard it has to push to get the amount of liquid you are moving from the pressure sensor to where it leaves the system. This pressure will depend on the product itself, the volume (gal/min) you are moving and how much restriction there is to that flow. The orifice or metering tube will be the primary restriction, but it is possible that other parts of the system may



add to the total pressure. 1/4" tubing can build a lot of pressure with 10-34-0. The pressure a system develops will be less (possibly much less) with water than it will be with a fertilizer product.

What pressure is "too low"?

You need enough pressure to open the check valves. If the pressure is too low, some check valves will open before others, so that some rows may be flowing while others are not. With 4 lb check valves, we like at least 8 PSI. With 10 lb check valves, we like 15-20 PSI.

What pressure is "too high"?

A pressure is too high if it keeps the system from being able to hit the rate you want or if it opens the PRV (Pressure Relief Valve) on a hydraulic pump.

The plumbing components of a SurePoint system are rated at 100 PSI or above. On an electric pump system, the pump capacity decreases as the pressure increases. Our standard Tower electric pump has an internal 70 PSI bypass. With an electric pump, we like to see pressures from 10 to 30 PSI. If the pump has the capacity to hit the rate at higher pressures, there is not a problem with doing that, but for long-term operation it would be best to switch to a larger orifice or metering tube. High pressure requires more current, which causes more voltage drop, which causes EPD problems.

The SurePoint PumpRight hydraulic pump has the ability to pump up to 290 PSI. SurePoint plumbs these with a 100 PSI pressure relief valve (PRV) so that plumbing components will not be damaged if high pressure develops. **Typical operating pressures with hydraulic pumps will be 20-60 PSI**, but the pump will work fine at 80-90 PSI if that is needed. If continually running in that high range, consider a larger orifice or metering tube.

Lower pressure will not necessarily reduce the **velocity of the output stream** at the row. Conversely, higher pressure will not necessarily increase the velocity of the output stream at the row. The velocity of the output stream is determined by the volume of the flow and the size of the opening at the output. Changing the pressure by changing an orifice or metering tube upstream from the outlet will not affect the velocity of the output stream if the flow volume remains the same.

Options if pressure is too high with orifices: Use a bigger orifice. Slow down. If pressure is too low, use a smaller orifice.

With metering tube: Options if pressure is too high: Use a larger diameter tube. Shorten the tubes that are on now. Slow down. (*The pressure in a metering tube is related to the viscosity of the product. Many products change viscosity as the temperature changes. A product will have a higher viscosity (and therefore higher pressure) on a cold morning than it will on a hot afternoon.)*

With metering tube: Options if pressure is too low: Switch to a smaller diameter tube. Use a longer tube.

See SurePoint publication "<u>396-3269Y1 Navigating the Metering Tube Maze</u>" or "<u>396-4116Y1 Metering</u> <u>Tube Charts</u>" for more information on how metering tube works.

See SurePoint publication "<u>396-3229Y1 Liquid System Components Overview</u>" for a description of all the system components and additional troubleshooting/service information.

See the system manual for your system for more complete information. Manuals and publications are available for download at www.surepointag.com.



Recommended Care and Maintenance

Winterization

SurePoint recommends flushing your fertilizer pump and complete system with adequate amounts of water first. Next, use RV antifreeze to winterize your system by pumping an adequate amount through all components. At the beginning of the next season, begin with water to verify the system is in working order with no leaks.



Inspect Electric Pumps

The electric pump and motor is a completely sealed component. Over time the electric motor will lose efficiency. The entire pump and motor will need replaced when it won't efficiently produce the flow required.

Each individual pump should be able to produce more than 4 gpm of water flow with an open outlet (zero pressure). If pump falls short of this specification, replace to ensure a trouble-free fertilizing operation.

You can test the operation of each pump individually by unplugging one pump and running one pump at a time. Compare the output of each pump to each other and to the standard above.

Pre-season Service

(A little time spent here may prevent some downtime when you want to be rolling.)

- 1. Visually check entire system (hoses, fittings, harnesses, etc.) for any signs of wear or trouble. Be sure pins are clean, not corroded, and are making good contact.
- 2. On the display, recheck all setup screens (see Section F) to verify correct setup.
- 3. Fill system with water and run in Manual mode to verify components and system are in working order. (May need to open air bleed valve to prime pump the first time. Be sure recirculation knob is closed.)
- 4. If pump runs but won't pump, tap on pump with a rubber mallet. If fertilizer was left in the system, you may need to pour hot water in the pump inlet to loosen the material.
- 5. Unplug one pump at a time to verify that each pump is operating as it should. Check GPM output of each pump.
- 6. Tighten all clamps. Loose clamps may be evident by leaks on the output side of the system. Loose clamps from the tank to the pump are not always apparent, but can be sources of air getting into the system which can create issues.
- 7. Push in all QuickConnect (QC) fittings to be sure the tubes are tightly seated. QC fittings that are not sealed can cause check valves to leak.
- 8. Remove the black cap from the top of each check valve. Check the diaphragm to be sure it is intact and not gummed up with residue. Look under the diaphragm for debris. Compress the spring in the cap to be sure it moves freely. Carefully replace diaphragm and tighten cap.
- 9. Remove and clean the strainer. Be sure strainer is tightened securely so it will not suck air.

9. Be sure all rows are flowing and that all metering tubes/orifices are open. (Note: It will take a higher flow rate with water to create enough pressure to open all the check valves so that each row will flow.)

10. Run system in Diagnostics > AUTO with speed and rate to be used in the field.

